


(19)  **Europäisches Patentamt**  
**European Patent Office**  
**Office européen des brevets**



(11) **EP 1 172 699 A1**

(12) **EUROPEAN PATENT APPLICATION**



(43) Date of publication:  
~~16.01.2002~~ Bulletin 2002/03

(51) Int Cl.7: **G03F 7/32, G03F 7/032,  
G03F 7/033, G03F 7/035**

(21) Application number: **01115798.9**

(22) Date of filing: **11.07.2001**

(84) Designated Contracting States:  
**AT BE CH CY DE DK ES FI FR GB GR IE IT LI LU  
MC NL PT SE TR**  
Designated Extension States:  
**AL LT LV MK RO SI**

(30) Priority: **14.07.2000 JP 2000214599  
12.09.2000 JP 2000276811**

(71) Applicant: **FUJI PHOTO FILM CO., LTD.  
Kanagawa (JP)**

(72) Inventors:  
• **Tsuchiya, Mitsumasa**  
**Yoshida-cho, Haibara-gun, Shizuoka (JP)**  
• **Nagase, Hiroyuki**  
**Yoshida-cho, Haibara-gun, Shizuoka (JP)**  
• **Kondo, Shunichi**  
**Yoshida-cho, Haibara-gun, Shizuoka (JP)**  
• **Kunita, Kazuto**  
**Yoshida-cho, Haibara-gun, Shizuoka (JP)**

(74) Representative: **HOFFMANN - EITLE**  
**Patent- und Rechtsanwälte Arabellastrasse 4**  
**81925 München (DE)**

(54) **Developing solution for photosensitive lithographic printing plate, plate-making method of lithographic printing plate, and photosensitive lithographic printing plate**

(57) A plate-making method of a lithographic printing plate is disclosed, which comprises the steps of exposure of a photosensitive lithographic printing plate having the acid value of a photosensitive layer of 1.0

meq/g or less with a laser beam, and then development with a developing solution having a pH value of 13.0 or less at a developing speed in an unexposed domain of 0.05  $\mu\text{m/s}$  or more and at an osmotic speed of a developing solution in an exposed domain of 0.1  $\mu\text{m/s}$  or less.

**EP 1 172 699 A1**

**Description****FIELD OF THE INVENTION**

5 [0001] The present invention relates to a novel developing solution for a photosensitive lithographic printing plate, a plate-making method of a lithographic printing plate, and a photosensitive lithographic printing plate. More specifically, the present invention relates to a developing solution optimal for a photopolymerizable lithographic printing plate which does not cause the reduction of developing properties with the lapse of time and repeated use, has good developing properties to a non-image domain (an unexposed domain) of a lithographic printing plate, prevents staining due to  
 10 printing, gives less damage due to development to an image domain (an exposed domain), forms a stable image, does not cause printing troubles during printing such as blinding, and realizing high printing durability. The present invention further relates to a plate-making method of a lithographic printing plate and a photosensitive lithographic printing plate.

**BACKGROUND OF THE INVENTION**

[0002] The developing solutions for photopolymerizable lithographic printing plates conventionally widely used are divided broadly into the following a) to c), i.e., a) a non-aqueous developing solution mainly comprising an organic solvent, b) an aqueous developing solution mainly comprising an inorganic alkali, and c) an aqueous developing solution mainly comprising an organic base.

[0003] Of the above three developing solutions, developing solutions b) and c) are used these days from the environmental demands.

[0004] Describing these two developing solutions in detail, a silicate is contained in the inorganic alkali developing solution b) near pH 12 for carrying out hydrophilizing treatment on a support generally after development.

[0005] A silicate is an essential component for performing hydrophilizing treatment, i.e., for preventing staining of a non-image domain at printing.

[0006] For example, the developing solution having pH of 12 or higher as disclosed in JP-A-8-248643 (the term "JP-A" as used herein means an "unexamined published Japanese patent application") and the developing solution having pH of 12 or lower as disclosed in JP-A-11-65129 are known as developing solution b). However, the former developing solution having pH of 12 or higher is liable to dissolve the aluminum used generally as a support, in particular when an image domain comprises minute dots, the aluminum support just under the image domain is dissolved by a side-etching phenomenon to cause the separation of minute dots from the support (dot-skipping) at printing, which extremely deteriorates a press life (i.e., a printing durability).

[0007] Further, a developing solution having pH of 12 or lower is preferred in the point of the above-described press life and the prevention of printing staining, but as a result of continuing development processing for a long period of time, pH is liable to lower due to the effect of, e.g., the carbon dioxide gas in the air, and the silicate precipitates in a developing solution at this time and development processing becomes unstable.

[0008] As an example of a developing solution, developing solutions not containing a silicate are disclosed in JP-A-61-109052, West German Patent 1,984,605, JP-A-2000-81711 and JP-A-11-65126, but all of these developing solutions are not only more disadvantageous than those containing a silicate in the point of the printing staining but the press life is also deteriorated.

[0009] On the other hand, as the organic base developing solution c), those containing an organic amine such as an ethanolamine and an alcohol-based organic solvent such as a benzyl alcohol as an auxiliary developing agent are known. The pH value of these developing solutions is certainly low, such as about 10, and so they are difficult to be affected by carbon dioxide gas and processing stability is good, but they are not only disadvantageous in the point of hydrophilization to a support, but also their osmotic power to an image domain is too high, thus there arises a problem that minute dots are separated from the support at development, i.e., an image-forming property is deteriorated.

[0010] That is, with respect to a photopolymerizable lithographic printing plate, a suitable developing solution is not found yet from the points of image-forming property, resistance to printing staining, printing durability and processing stability.

[0011] With respect to the composition of a developing solution, it is known that whether silicate is contained or not, whether pH is high or low, and the difference between an inorganic alkali and an organic alkali greatly influence a development phenomenon but conventional combinations cannot solve the above problems.

[0012] Further, when development processing of a photopolymerizable lithographic printing plate is continued for a long period of time, insoluble substance is accumulated, agglomerated, precipitated and becomes development scum, which becomes a main cause of making development processing unstable.

[0013] The components of such development scum have not been clearly known until now but it was found from the analysis that much of the scum was insoluble components of a developing solution contained in a photosensitive layer.

[0014] As the insoluble components, e.g., various kinds of colorants which are added to a photosensitive layer for the purpose of discriminating an exposed domain from an unexposed domain can be exemplified. In the case of photopolymerizable lithographic printing plates, for the purpose of avoiding desensitization due to radical supplement and desensitization due to unnecessary interaction (energy transfer and electron transfer) with an initiator system (an initiator alone, or combination of an initiator with a sensitizing dye), a pigment is used as the colorant which is not molecularly dispersed in a photosensitive layer but is dispersed as an aggregate with maintaining a crystalline state. However, these pigment are substantially insoluble in a developing solution, therefore they are at first temporarily dispersed in a developing solution in a development step for removing an unexposed area but when development processing is continued for a long period of time, they are accumulated, agglomerated, precipitated and come to development scum.

[0015] On the other hand, various photopolymerization initiators (radical generating agents) are used in a photopolymerizable lithographic printing plate to cope with laser light sources which are making progress in recent years. Of these initiators, titanocene-based initiators are known as the initiators which have photosensitivity in the wavelength of laser light source and excellent in stability and sensitivity. However, titanocene-based initiators are organic metals and insoluble in a developing solution similar to the above pigments, and temporarily dispersed in a developing solution but when development processing is continued for a long period of time, they are accumulated, agglomerated, precipitated and also come to development scum.

[0016] With respect to the processing stability, it is very important to solve not only the problem of the precipitation of silicate with the reduction of pH but also the problem of development scum.

[0017] That is, as the developing solution for a photopolymerizable lithographic printing plate, a developing solution which satisfies the above-described image-forming property, the compatibility of printing staining resistance with printing durability, and processing stability is desired.

[0018] Further, since conventionally broadly used negative type photosensitive lithographic printing plates are comprising a hydrophilized aluminum plate having provided thereon a diazo resin, the use of an organic solvent in a developing solution cannot be helped, hence there are fears of the disposal of developing waste solution and the influence to the environment. Further, an orthoquinonediazide compound is used in combination with a novolak resin in a photosensitive layer of a positive type photosensitive lithographic printing plate, and an alkaline aqueous solution of silicate which can dissolve a novolak resin is used in a developing solution. However, the pH value capable of dissolving a novolak resin is 13 or so, and if a developing solution having such high pH is attached to the skin or a mucous membrane, it irritate the skin hard, hence sufficient care should be taken to handle it.

[0019] On the other hand, a photosensitive lithographic printing plate comprising an aluminum support having a photosensitive layer of a photopolymerizable photosensitive lithographic printing plate is also used and aqueous solutions of silicate, phosphate, carbonate and hydroxide of alkali metal and an organic amine compound are proposed as the developing solution.

[0020] For example, a developing solution having pH of 12 or more and containing silicic acid alkali salt and an amphoteric surfactant is disclosed in JP-A-8-248643, and a developing solution containing silicic acid alkali silicate defined by  $\text{SiO}_2/\text{M}_2\text{O}$  (M represents an alkali metal) having a pH of 12 or less is disclosed in JP-A-11-65129.

[0021] The former has a problem that an image domain is liable to be damaged by development due to high pH value of the developing solution in addition to a problem of handling, and the latter has a problem that silicate gels and is insolubilized with the slight reduction of the pH value of the developing solution during use.

[0022] As developing solutions not containing silicic acid alkali salt, a developing solution comprising an alkali reagent, a complexing agent, an anionic surfactant, an emulsifying agent, an n-alkanic acid, etc., is disclosed in JP-A-61-109052, and a developing solution comprising an alkali agent, a complexing agent, an anionic surfactant, an amyl alcohol, N-alkoxylamines, etc., is disclosed in West German Patent 1,984,605, but the damage to an image domain is great due to their high pH values and organic solvents contained, and sufficient printing properties, such as press life, cannot be obtained.

[0023] As a developing solution having relatively low pH (12 or less) and not containing silicic acid alkali, a developing solution comprising an aqueous solution of potassium hydroxide containing an anionic surfactant is disclosed in JP-A-2000-81711, and a developing solution comprising an aqueous solution of alkali metal carbonate having pH of from 8.5 to 11.5 is disclosed in JP-A-11-65126.

[0024] However, since these developing solutions having relatively low pH are fundamentally poor in dissolving power of photopolymerizable photosensitive layer, development does not progress sufficiently with a printing plate after the lapse of time, as a result the problem of residual film arises. For resolving these problems, it is necessary to contrive to increase the acid value of the high polymer binder in a photosensitive layer to thereby improve developing property, or use a monomer having an acid radical in combination. However, when such a binder having high acid value is used, printing troubles during printing, e.g., a trouble that ink comes to not adhere during printing (blinding), are liable to occur.

**SUMMARY OF THE INVENTION**

**[0025]** Accordingly, the objects of the present invention are to provide a developing solution for a photosensitive lithographic printing plate by which the above-described weak points of conventional techniques can be overcome, an image-forming property is not damaged, staining resistance during printing can be compatible with printing durability, the above-described insoluble compounds in a developing solution can be dissolved or dispersed stably for long time, and processing stability can be improved, and provide a plate-making method of a lithographic printing plate and a photosensitive lithographic printing plate.

**[0026]** A further object of the present invention is to provide a plate-making method of a lithographic printing plate using an alkali developing solution having comparatively low pH which is preferable in environment and safety, in which plate-making method can produce a lithographic printing plate having a preferred non-image domain stably having good developing property without staining due to printing, can give less damage by development to an image domain, can form a stable image without printing troubles during printing such as blinding, and can realize high printing durability.

**[0027]** As a result of eager investigation by the present inventors, the above objects of the present invention have been achieved by the following means.

**[0028]** That is, the embodiments of the present invention are as follows.

(1) A plate-making method of a lithographic printing plate which comprises the steps of exposure of a photosensitive lithographic printing plate having the acid value of a photosensitive layer of 1.0 meq/g or less with a laser beam, and then development with a developing solution having a pH of 13.0 or less at a developing speed in an unexposed domain of 0.05  $\mu\text{m/s}$  or more and at an osmotic speed of a developing solution in an exposed domain of 0.1  $\mu\text{m/s}$  or less.

(2) A plate-making method of a lithographic printing plate which comprises the steps of exposure of a photosensitive lithographic printing plate having the acid value of a photosensitive layer of 1.0 meq/g or less with a laser beam, and then development with a developing solution having a pH value of 13.0 or less so as to dissolve the photosensitive layer in order from the surface without swelling and peeling of the photosensitive layer.

(3) A developing solution for a photosensitive lithographic printing plate which is a non-silicate-based developing solution and contains an inorganic alkali agent and a nonionic compound represented by the following formula (I) :



wherein A represents a hydrophobic organic group having 1.5 or more of logP of A-H, and W represents a hydrophilic organic group having less than 1.0 of logP of W-H.

(4) The developing solution for a photosensitive lithographic printing plate as described in the above item (3), which contains a chelating agent to a divalent metal.

(5) The developing solution for a photosensitive lithographic printing plate as described in the above item (3), which has a pH of from 10.0 to 12.5 and electrical conductance of from 3 to 30 mS/cm.

(6) The developing solution for a photosensitive lithographic printing plate as described in the above item (3), which contains a carbonic acid or a carbonate.

(7) The plate-making method of a lithographic printing plate as described in the above item (1) or (2), wherein the photosensitive lithographic printing plate is a photopolymerizable lithographic printing plate having on a support a photopolymerizable photosensitive layer containing the following i) and ii) as essential components:

- i) a compound having an addition polymerizable ethylenically unsaturated bond, and
- ii) a photopolymerization initiator.



(8) The plate-making method of a lithographic printing plate as described in the above item (7), wherein the photopolymerizable photosensitive layer contains a titanocene-based initiator or a colorant (e.g., a pigment).

(9) The plate-making method of a lithographic printing plate as described in the above item (7), wherein the support is an anodized aluminum support containing an organic compound having a phosphorus-containing atomic group on the surface of the support.

(10) A photosensitive lithographic printing plate comprising a photopolymerizable photosensitive layer, wherein the photosensitive layer contains a compound having an acid radical having a pKa of 9 or less and the acid value of the photosensitive layer is from 0.20 to 0.60 meq/g.

(11) A plate-making method of a lithographic printing plate which comprises the steps of image exposure of a photosensitive lithographic printing plate comprising an aluminum support having an anodized film on the surface having provided thereon a photopolymerizable photosensitive layer containing a compound having an addition

polymerizable ethylenically unsaturated double bond, a high polymer soluble or swelling in an alkaline aqueous solution, and a photopolymerization initiator with a laser beam, and then development with a developing solution comprising an alkaline aqueous solution containing at least one of a nonionic aromatic ether-based activator represented by the following formula (I-A) and a nonionic aromatic ether-based activator represented by the following formula (I-B):



wherein  $R_1$  and  $R_2$  each represents H or an alkyl group having from 1 to 100 carbon atoms, and  $n$  and  $m$  each represents an integer of from 0 to 100.

(12) A plate-making method of a lithographic printing plate which comprises the steps of image exposure of a photosensitive lithographic printing plate comprising an aluminum support having provided thereon a photopolymerizable photosensitive layer containing a compound having an ethylenically unsaturated double bond, a photopolymerization initiator and a high polymer binder, and then development with a developing solution containing an inorganic alkali agent and a nonionic surfactant having a polyoxyalkylene ether group, having a pH of from 10.0 to 12.5, and an electrical conductance of from 3 to 30 mS/cm.

**[0029]** As a result of eager investigations of developing solution compositions, resistance to printing staining could be compatible with printing durability without impairing an image-forming property, the above-described insoluble compounds in a developing solution could be dissolved or dispersed stably for long time, and processing stability could be improved by using a developing solution comprising special components.

**[0030]** At present, the special developing solution is thought to be the developing solution composition which satisfies the following requisites.

**[0031]** First, to be capable of extraordinarily well functioning to image-forming property (the developing property at an unexposed domain is high, the osmotic property of a developing solution to an exposed domain is low, and dissolution behavior of a photosensitive layer is non-swelling and a photosensitive layer is dissolved in order from the surface).

**[0032]** Secondly, to be capable of excluding the unexposed domain of a photosensitive layer completely and reclaiming the support surface as a hydrophilic layer generating no printing staining.

**[0033]** Thirdly, for stably dispersing or solubilizing the above-described compounds insoluble in a developing solution, a nonionic compound represented by formula (I) having a hydrophilic site to be dispersed and stabilized with a hydrophobic site interacting with these insoluble compounds must be contained.

**[0034]** Fourthly, the concentration of salt must be low to prevent salting out and the reduction of a developing speed (the developing solution must be non-silicate-based and the pH must be low as compared with conventionally used alkali developing solutions).

**[0035]** Fifthly, to contain a chelating agent to remove a divalent metal such as a Ca ion contained in water which is an unstabilizing factor at development processing.

**[0036]** Of these, with respect to the first and second requisites, the characteristics of photosensitive layer components are also important factors. The photosensitive layer of a photopolymerizable lithographic printing plate is not restricted particularly, but until the present it is known that having lower photosensitive layer acid value than conventional acid value is thought to be important to obtain a synergistic effect with the developing solution according to the present invention.

**[0037]** The present inventors have found that, by combining an alkali solution having relatively low pH with a nonionic surfactant having special structure, and adjusting the salt concentration in the developing solution, the dissolving speed of the unexposed domain of a photopolymerizable photosensitive layer increases and, contrary to this, the osmosis of the developing solution is controlled in the area crosslinked by polymerization of the exposed domain, thus the present

invention has been accomplished.

[0038] Therefore, a printing plate comprising an unexposed domain having no printing staining and an exposed domain having high press life (i.e., high printing durability) can be obtained stably according to the present invention.

## **BRIEF DESCRIPTION OF THE ACCOMPANYING DRAWINGS**

[0039] Fig. 1 is a schematic diagram of an apparatus for measuring the osmotic speed of a developing solution.

[0040] Fig. 2 is a graph for measuring the osmotic speed of a developing solution.

[0041] Fig. 3 is a schematic diagram of a DRM coherent wave-measuring apparatus for measuring the dissolution and swelling of a photosensitive layer.

[0042] Fig. 4 is a graph for measuring the dissolution and swelling of a photosensitive layer.

[0043] In these figures, the Numerals denote the following members, respectively.

1. Support
2. Recoding Layer
3. Electrode
4. Developing solution
5. Photosensitive Layer
6. Photosensitive Material

## **DETAILED DESCRIPTION OF THE INVENTION**

[0044] A developing solution for a photosensitive lithographic printing plate, a plate-making method and a photosensitive lithographic printing plate according to the present invention are described in detail below.

[0045] In the first place, developing behavior is described in detail below.

### Developing speed

[0046] The developing speed used in the present invention is defined as follows: A lithographic printing plate precursor obtained in Example 1 described later is immersed as it is without exposure in various kinds of developing solutions at 28°C, and the time until the photosensitive layer is removed and the support appears is measured. The developing speed to the film thickness of the photosensitive layer is calculated. The higher the developing speed, the greater and the better is the developing property.

[0047] Developing speed of the unexposed domain = film thickness of photosensitive layer ( $\mu\text{m}$ )/development completed time (s)

### Osmotic speed of developing solution

[0048] The osmotic speed of a developing solution used in the present invention is defined as follows: A lithographic printing plate precursor obtained in Example 1 described later is subjected to exposure, then immersed in various kinds of developing solutions at 28°C, and the change of electrostatic capacity is measured. By measuring the time when the change of electrostatic capacity begins, the time required for the developing solution to osmose and come into contact with the support can be found (when the changing point does not appear clearly, it is estimated by the time required for the electrostatic capacity to reach 100 nF). The osmotic speed of a developing solution in the direction of the photosensitive layer thickness is computed from the above-found time. The smaller the speed, the lower and the better is the osmotic property. An apparatus for measuring the osmotic speed of a developing solution and a graph for measuring are shown in Figs. 1 and 2 respectively.

[0049] Osmotic speed of a developing solution in the exposed domain = photosensitive layer thickness ( $\mu\text{m}$ )/time when the change of electrostatic capacity begins (s)

[0050] An apparatus for measuring the osmotic speed of a developing solution and a graph for measuring are shown in Figs. 1 and 2, respectively.

### Dissolution and swelling of photosensitive layer

[0051] The dissolution and swelling of a photosensitive layer is defined as follows: A lithographic printing plate precursor obtained in Example 1 described later is immersed as it is without exposure in various kinds of developing solutions at 30°C, and the dissolution behavior of the photosensitive layer is measured by a DRM coherent wave-measuring apparatus. When development behavior is non-swelling development starting from the surface of a photo-

sensitive layer, the photosensitive layer thickness becomes gradually thin to the developing time and a clear coherent wave corresponding to the thickness can be obtained. Contrary to this, in the case of swelling dissolution (or dissolution not depending upon film), a clear coherent wave cannot be obtained, since the layer thickness changes according to the osmosis of a developing solution.

**[0052]** It is preferred that a clear coherent wave can be obtained, and evaluation is performed by the presence or absence of a coherent wave.

**[0053]** A DRM coherent wave-measuring apparatus for measuring the dissolution and swelling of a photosensitive layer and a graph for measuring are shown in Figs. 3 and 4 respectively.

**[0054]** The components of the developing solution according to the present invention are described in detail below.

Nonionic compound represented by formula (I)

**[0055]**

A-W

(1)

wherein A represents a hydrophobic organic group having 1.5 or more of logP of A-H, and W represents a hydrophilic organic group having less than 1.0 of logP of W-H.

**[0056]**  $\log P$  is generally used as a hydrophobic parameter as described in C. Hansch, A. Leo, Substituent Constants for Correlation Analysis in Chemistry and Biology, John Wiley & Sons, Inc. (1979), and is defined as the logarithm of equilibrium concentration ratio  $P$  computed from the ratio divided to each layer of two layer system of octanol/water of the objective molecules (A-H and W-H).

**[0057]** Here each group of A and W in formula (I) is used as a specified characteristic, and logP value is computed from well-known data based on the method described in A.K. Ghose, et al., J. Comput. Chem., 9, 80 (1988) as to A-H and A-W, i.e., these are the structures of organic groups A and W to each of which a hydrogen atom is bonded for convenience' sake.

**[0058]** Specifically, organic groups A and W are different from each other in structure, and each represents a monovalent organic residue which satisfies the above logP. More preferably, A and W, which may be the same or different, each represents a hydrogen atom, a halogen atom, a hydrocarbon group which may have a substituent and may contain an unsaturated bond, a heterocyclic group, a hydroxyl group, a substituted oxy group, a mercapto group, a substituted thio group, an amino group, a substituted amino group, a substituted carbonyl group, a carboxylate group, a sulfo group, a sulfonato group, a substituted sulfinyl group, a substituted sulfonyl group, a phosphono group, a substituted phosphono group, a phosphonato group, a substituted phosphonato group, a cyano group, or a nitro group.

**[0059]** As the above hydrocarbon group which may have a substituent and may contain an unsaturated bond, an alkyl group, a substituted alkyl group, an aryl group, a substituted aryl group, an alkenyl group, a substituted alkenyl group, an alkynyl group and a substituted alkynyl group can be exemplified.

**[0060]** As the alkyl groups, a straight chain, branched or cyclic alkyl group having from 1 to 20 carbon atoms can be exemplified, and specific examples thereof include a methyl group, an ethyl group, a propyl group, a butyl group, a pentyl group, a hexyl group, a heptyl group, an octyl group, a nonyl group, a decyl group, a undecyl group, a dodecyl group, a tridecyl group, a hexadecyl group, an octadecyl group, an eicosyl group, an isopropyl group, an isobutyl group, an s-butyl group, a t-butyl group, an isopentyl group, a neopentyl group, a 1-methylbutyl group, an isohexyl group, a 2-ethylhexyl group, a 2-methylhexyl group, a cyclohexyl group, a cyclopentyl group, and a 2-norbornyl group. Of these groups, a straight chain alkyl group having from 1 to 12 carbon atoms, a branched alkyl group having from 3 to 12 carbon atoms, and a cyclic alkyl group having from 5 to 10 carbon atoms are more preferred.






**[0061]** The substituted alkyl group is made by bonding a substituent with an alkylene group, and monovalent non-metallic atomic groups exclusive of a hydrogen atom are used as the substituents. Preferred examples of the substituents of the substituted alkyl group include a halogen atom (-F, -Br, -Cl, -I), a hydroxyl group, an alkoxy group, an aryloxy group, a mercapto group, an alkylthio group, an arylthio group, an alkyldithio group, an aryldithio group, an amino group, an N-alkylamino group, an N,N-dialkylamino group, an N-arylamino group, an N,N-diarylamino group, an N-alkyl-N-arylamino group, an acyloxy group, a carbamoyloxy group, an N-alkylcarbamoyloxy group, an N-arylcarbamoyloxy group, an N,N-dialkylcarbamoyloxy group, an N,N-diarylcarbamoyloxy group, an N-alkyl-N-arylcarbamoyloxy group, an alkylsulfoxy group, an arylsulfoxy group, an acylthio group, an acylamino group, an N-alkylacylamino group, an N-arylacylamino group, a ureido group, an N'-alkylureido group, an N',N'-dialkylureido group, an N'-arylureido group, an N',N'-diarylureido group, an N'-alkyl-N'-arylureido group, an N-alkylureido group, an N-arylureido group, an N'-alkyl-N-alkylureido group, an N'-alkyl-N-arylureido group, an N',N'-dialkyl-N-alkylureido group, an N',N'-dialkyl-N-arylureido group, an N'-aryl-N-alkylureido group, an N'-aryl-N-arylureido group, an N',N'-diaryl-N-alkylureido group, an N',N'-diaryl-N-arylureido group, an N'-alkyl-N'-aryl-N-alkylureido group, an N'-alkyl-N'-aryl-N-arylureido group, an

alkoxycarbonylamino group, an aryloxycarbonylamino group, an N-alkyl-N-alkoxycarbonylamino group, an N-alkyl-N-aryloxycarbonylamino group, an N-aryl-N-alkoxycarbonylamino group, an N-aryl-N-aryloxycarbonylamino group, a formyl group, an acyl group, a carboxyl group and a conjugate base group of it (hereinafter referred to as a carboxylate group), an alkoxycarbonyl group, an aryloxycarbonyl group, a carbamoyl group, an N-alkylcarbamoyl group, an N,N-dialkylcarbamoyl group, an N-arylcarbamoyl group, an N,N-diarylcarbamoyl group, an N-alkyl-N-arylcarbamoyl group, an alkylsulfinyl group, an arylsulfinyl group, an alkylsulfonyl group, an arylsulfonyl group, a sulfo group ( $-\text{SO}_3\text{H}$ ) and a conjugate base group of it (hereinafter referred to as a sulfonate group), an alkoxysulfonyl group, an aryloxysulfonyl group, a sulfamoyl group, an N-alkylsulfamoyl group, an N,N-dialkylsulfamoyl group, an N-arylsulfamoyl group, an N,N-diarylsulfamoyl group, an N-alkyl-N-arylsulfamoyl group, a sulfamoyl group, an N-alkylsulfamoyl group, an N,N-dialkylsulfamoyl group, an N-arylsulfamoyl group, an N,N-diarylsulfamoyl group, an N-alkyl-N-arylsulfamoyl group, an N-acylsulfamoyl group and a conjugate base group of it, an N-alkylsulfonylsulfamoyl group ( $-\text{SO}_2\text{NHSO}_2(\text{alkyl})$ ) and a conjugate base group of it, an N-arylsulfonylsulfamoyl group ( $-\text{SO}_2\text{NHSO}_2(\text{aryl})$ ) and a conjugate base group of it, an N-alkylsulfonylcarbamoyl group ( $-\text{CONHSO}_2(\text{alkyl})$ ) and a conjugate base group of it, an N-arylsulfonylcarbamoyl group ( $-\text{CONHSO}_2(\text{aryl})$ ) and a conjugate base group of it, an alkoxysilyl group ( $-\text{Si}(\text{Oalkyl})_3$ ), an aryloxysilyl group ( $-\text{Si}(\text{Oaryl})_3$ ), a hydroxysilyl group ( $-\text{Si}(\text{OH})_3$ ) and a conjugate base group of it, a phosphono group ( $-\text{PO}_3\text{H}_2$ ) and a conjugate base group of it (hereinafter referred to as a phosphonate group), a dialkylphosphono group ( $-\text{PO}_3(\text{alkyl})_2$ ), a diarylphosphono group ( $-\text{PO}_3(\text{aryl})_2$ ), an alkylarylphosphono group ( $-\text{PO}_3(\text{alkyl})(\text{aryl})$ ), a monoalkylphosphono group ( $-\text{PO}_3\text{H}(\text{alkyl})$ ) and a conjugate base group of it (hereinafter referred to as an alkylphosphonate group), a monoarylphosphono group ( $-\text{PO}_3\text{H}(\text{aryl})$ ) and a conjugate base group of it (hereinafter referred to as an arylphosphonate group), a phosphonooxy group ( $-\text{OPO}_3\text{H}_2$ ) and a conjugate base group of it (hereinafter referred to as a phosphonatoxy group), a dialkylphosphonooxy group ( $-\text{OPO}_3(\text{alkyl})_2$ ), a diarylphosphonooxy group ( $-\text{OPO}_3(\text{aryl})_2$ ), an alkylarylphosphonooxy group ( $-\text{OPO}_3(\text{alkyl})(\text{aryl})$ ), a monoalkylphosphonooxy group ( $-\text{OPO}_3\text{H}(\text{alkyl})$ ) and a conjugate base group of it (hereinafter referred to as an alkylphosphonatoxy group), a monoarylphosphonooxy group ( $-\text{OPO}_3\text{H}(\text{aryl})$ ) and a conjugate base group of it (hereinafter referred to as an arylphosphonatoxy group), a cyano group, a nitro group, an aryl group, an alkenyl group, and an alkynyl group.

**[0062]** As the specific examples of the alkyl groups in the substituents of the substituted alkyl groups, the above-described alkyl groups can be exemplified. As the specific examples of the aryl groups in the substituents of the substituted alkyl groups, a phenyl group, a biphenyl group, a naphthyl group, a tolyl group, a xylyl group, a mesityl group, a cumenyl group, a fluorophenyl group, a chlorophenyl group, a bromophenyl group, a chloromethylphenyl group, a hydroxyphenyl group, a methoxyphenyl group, an ethoxyphenyl group, a phenoxyphenyl group, an acetoxypheyl group, a benzoyloxyphenyl group, a methylthiophenyl group, a phenylthiophenyl group, a methylaminophenyl group, a dimethylaminophenyl group, an acetylaminophenyl group, a carboxyphenyl group, a methoxycarbonylphenyl group, an ethoxycarbonylphenyl group, a phenoxycarbonylphenyl group, an N-phenylcarbamoylphenyl group, a phenyl group, a nitrophenyl group, a cyanophenyl group, a sulfophenyl group, a sulfonatophenyl group, a phosphonophenyl group and a phosphonatophenyl group can be exemplified. As the examples of the alkenyl groups in the substituents of the substituted alkyl groups, a vinyl group, a 1-propenyl group, a 1-butenyl group, a cinnamyl group, and a 2-chloro-1-ethenyl group can be exemplified, and as the examples of the alkynyl groups in the substituents of the substituted alkyl groups, an ethynyl group, a 1-propynyl group, a 1-butylnyl group, a trimethylsilylethynyl group and a phenylethynyl group can be exemplified.

**[0063]** As  $\text{R}^4$  in the acyl group ( $\text{R}^4\text{CO}-$ ) in the substituents of the substituted alkyl groups, a hydrogen atom and the above-described alkyl groups, aryl groups, alkenyl groups and alkynyl groups can be exemplified. On the other hand, as the alkylene group in the substituted alkyl group, the alkylene groups obtained by removing any one hydrogen atom on the above-described alkyl groups having from 1 to 20 carbon atoms to make divalent organic residues can be exemplified, preferably a straight chain alkylene group having from 1 to 12 carbon atoms, a branched alkylene group having from 3 to 12 carbon atoms, and a cyclic alkylene group having from 5 to 10 carbon atoms are exemplified. Specific examples of the preferred substituted alkyl groups include a chloromethyl group, a bromomethyl group, a 2-chloroethyl group, a trifluoromethyl group, a methoxymethyl group, a methoxyethoxyethyl group, an allyloxymethyl group, a phenoxymethyl group, a methylthiomethyl group, a tolylthiomethyl group, an ethylaminoethyl group, a diethylaminopropyl group, a morpholinopropyl group, an acetyloxymethyl group, a benzoyloxymethyl group, an N-cyclohexylcarbamoyloxyethyl group, an N-phenylcarbamoyloxyethyl group, an acetylaminooethyl group, an N-methylbenzoylaminopropyl group, a 2-oxoethyl group, a 2-oxopropyl group, a carboxypropyl group, a methoxycarbonylethyl group, a methoxycarbonylmethyl group, a methoxycarbonylbutyl group, an ethoxycarbonylmethyl group, a butoxycarbonylmethyl group, an allyloxycarbonylmethyl group, a benzyloxycarbonylmethyl group, a methoxycarbonylphenylmethyl group, a trichloromethylcarbonylmethyl group, an allyloxycarbonylbutyl group, a chlorophenoxycarbonylmethyl group, a carbamoylmethyl group, an N-methylcarbamoylethyl group, an N,N-dipropylcarbamoylmethyl group, an N-(methoxyphenyl)carbamoylethyl group, an N-methyl-N-(sulfophenyl) carbamoylmethyl group, a sulfopropyl group, a sulfobutyl group, a sulfonatobutyl group, a sulfamoylbutyl group, an N-ethylsulfamoylmethyl group, an N,N-dipropylsulfamoylpropyl group, an N-tolylsulfamoylpropyl group, an N-methyl-N-(phosphonophenyl)sulfamoyloctyl group,












a phosphonobutyl group, a phosphonatohexyl group, a diethylphosphonobutyl group, a diphenylphosphonopropyl group, a methylphosphonobutyl group, a methylphosphonatobutyl group, a tolylphosphonoethyl group, a tolylphosphonatohexyl group, a phosphonoxypropyl group, a phosphonatoxybutyl group, a benzyl group, a phenethyl group, an  $\alpha$ -methylbenzyl group, a 1-methyl-1-phenylethyl group, a p-methylbenzyl group, a cinnamyl group, an allyl group, a 1-propenylmethyl group, a 2-butenyl group, a 2-methylallyl group, a 2-methylpropenylmethyl group, a 2-propynyl group, a 2-butyryl group, and a 3-butyryl group.

**[0064]** As the aryl groups, a condensed ring formed by 1 to 3 benzene rings and a condensed ring formed by a benzene ring and a 5-membered unsaturated ring can be exemplified, and specific examples include a phenyl group, a naphthyl group, an anthryl group, a phenanthryl group, an indenyl group, an acenabutenyl group, and a fluorenyl group. Of these, a phenyl group and a naphthyl group are more preferred.

**[0065]** The substituted aryl group is that obtained by bonding a substituent to an aryl group, and those having a monovalent non-metallic atomic groups exclusive of a hydrogen atom on the ring-forming carbon atoms of the above-described aryl groups as the substituent are used. As preferred examples of the substituents, the above-described alkyl groups, substituted alkyl groups, and those described above as the examples of the substituents in the substituted alkyl groups can be exemplified. Preferred specific examples of these substituted aryl groups include a biphenyl group, a tolyl group, a xylyl group, a mesityl group, a cumenyl group, a chlorophenyl group, a bromophenyl group, a fluorophenyl group, a chloromethylphenyl group, a trifluoromethylphenyl group, a hydroxyphenyl group, a methoxyphenyl group, a methoxyethoxyphenyl group, an allyloxyphenyl group, a phenoxyphenyl group, a methylthiophenyl group, a tolylthiophenyl group, a phenylthiophenyl group, an ethylaminophenyl group, a diethylaminophenyl group, a morpholinophenyl group, an acetyloxyphenyl group, a benzoyloxyphenyl group, an N-cyclohexylcarbamoyloxyphenyl group, an N-phenylcarbamoyloxyphenyl group, an acetaminophenyl group, an N-methylbenzoylaminophenyl group, a carboxyphenyl group, a methoxycarbonylphenyl group, an allyloxycarbonylphenyl group, a chlorophenoxycarbonylphenyl group, a carbamoylphenyl group, an N-methylcarbamoylphenyl group, an N,N-dipropylcarbamoylphenyl group, an N-(methoxyphenyl)carbamoylphenyl group, an N-methyl-N-(sulfophenyl) carbamoylphenyl group, a sulfophenyl group, a sulfonatophenyl group, a sulfamoylphenyl group, an N-ethylsulfamoylphenyl group, an N,N-dipropylsulfamoylphenyl group, an N-tolylsulfamoylphenyl group, an N-methyl-N-(phosphonophenyl)sulfamoylphenyl group, a phosphonophenyl group, a phosphonatophenyl group, a diethylphosphonophenyl group, a diphenylphosphonophenyl group, a methylphosphonophenyl group, a tolylphosphonophenyl group, a tolylphosphonatophenyl group, an allyl group, a 1-propenylmethyl group, a 2-butenyl group, a 2-methylallylphenyl group, a 2-methylprope-


nylphenyl group, a 2-propynylphenyl group, a 2-butynylphenyl group, and a 3-butynylphenyl group.









[0066] As the examples of the alkenyl groups, the groups described above can be used. The substituted alkenyl group is that in which a substituent is bonded to the alkenyl group by replacing with the hydrogen atom in the alkenyl group, and as the substituents of the substituted alkenyl group, the substituents exemplified above in the substituted alkyl group can be used. As the alkenyl group, the above-described alkenyl groups can be used. As the preferred examples of the substituted alkenyl groups, the following compounds can be exemplified.




[0067] As the examples of the alkynyl groups, the groups described above can be used. The substituted alkynyl group is that in which a substituent is bonded to the alkynyl group by replacing with the hydrogen atom in the alkynyl group, and as the substituents of the substituted alkynyl group, the substituents exemplified above in the substituted alkyl group can be used. As the alkynyl group, the above-described alkynyl groups can be used.

[0068] The heterocyclic group is a monovalent group (a substituted heterocyclic group) obtained by removing one hydrogen atom from a heterocyclic ring, further removing one hydrogen atom from this monovalent group, and bonding the substituent in the above-described substituted alkyl group thereto. The preferred examples of the heterocyclic groups are shown below.







5



,




,




,


10



,




,




,

15


20



,




,




,

25


30



,




,




,


35




,



,




,




,


40




,



,




,




,

45


50




,



,




,



,

55



**[0069]** As the substituted oxy groups ( $R^5O-$ ), those in which  $R^5$  represents a monovalent non-metallic atomic group exclusive of a hydrogen atom can be used. The preferred examples of the substituted oxy groups include an alkoxyl group, an aryloxy group, an acyloxy group, a carbamoyloxy group, an N-alkylcarbamoyloxy group, an N-arylcarbamoyloxy group, an N,N-dialkylcarbamoyloxy group, an N,N-diarylcarbamoyloxy group, an N-alkyl-N-arylcarbamoyloxy group, an alkylsulfoxy group, an arylsulfoxy group, a phosphonooxy group, and a phosphonatoxy group. As the alkyl group and the aryl group in these substituted oxy groups, the above-described alkyl groups, substituted alkyl groups, aryl groups and substituted aryl groups can be exemplified. As  $R^6$  in the acyl group ( $R^6CO-$ ) in the acyloxy groups, the above-described alkyl groups, substituted alkyl groups, aryl groups, and substituted aryl groups can be exemplified. Of the above substituted oxy groups, an alkoxyl group, an aryloxy group, an acyloxy group, and an arylsulfoxy group are more preferred. The specific examples of the preferred substituted oxy groups include a methoxy group, an ethoxy group, a propyloxy group, an isopropyloxy group, a butyloxy group, a pentyloxy group, a hexyloxy group, a dodecyloxy group, a benzyloxy group, an allyloxy group, a phenethyloxy group, a carboxyethyloxy group, a methoxycarbonylethoxy group, an ethoxycarbonylethoxy group, a methoxyethoxy group, a phenoxyethoxy group, a methoxyethoxyethoxy group, an ethoxyethoxyethoxy group, a morpholinoethoxy group, a morpholinopropoxy group, an allyloxyethoxy group, an ethoxyethoxyethoxy group, a tolyloxy group, a xilyloxy group, a mesityloxy group, a cumenyloxy group, a methoxyphenyloxy group, an ethoxyphenyloxy group, a chlorophenyloxy group, a bromophenyloxy group, an acetyloxy group, a benzoyloxy group, a naphthyloxy group, a phenylsulfonyloxy group, a phosphonooxy group, and a phosphonatoxy group.

**[0070]** As the substituted thio groups ( $R^7S-$ ), those in which  $R^7$  represents a monovalent non-metallic atomic group exclusive of a hydrogen atom can be used. The preferred examples of the substituted thio groups include an alkylthio group, an arylthio group, an alkylidithio group, an arylidithio group and an acylthio group. As the alkyl group and the aryl group in these substituted thio groups, the above-described alkyl groups, substituted alkyl groups, aryl groups, and substituted aryl groups can be exemplified.  $R^6$  in the acyl group ( $R^6CO-$ ) in the acylthio groups is the same as described above. Of the above-described substituted thio groups, an alkylthio group and an arylthio group are more preferred. The specific examples of the preferred substituted thio groups include a methylthio group, an ethylthio group, a phenylthio group, an ethoxyethylthio group, a carboxyethylthio group, and a methoxycarbonylthio group.

**[0071]** As the substituted amino groups ( $R^8NH-$ , ( $R^9$ ) ( $R^{10}N-$ ), those in which  $R^8$ ,  $R^9$  and  $R^{10}$  each represents a monovalent non-metallic atomic group exclusive of a hydrogen atom can be used. The preferred examples of the substituted amino groups include an N-alkylamino group, an N,N-dialkylamino group, an N-arylamino group, an N,N-diarylamino group, an N-alkyl-N-arylamino group, an acylamino group, an N-alkylacylamino group, an N-arylacylamino group, a ureido group, an N'-alkylureido group, an N',N'-dialkylureido group, an N'-arylureido group, an N',N'-diarylureido group, an N'-alkyl-N'-arylureido group, an N-alkylureido group, an N-arylureido group, an N'-alkyl-N-alkylureido group, an N'-alkyl-N-arylureido group, an N',N'-dialkyl-N-alkylureido group, an N',N'-dialkyl-N-arylureido group, an N'-aryl-N-alkylureido group, an N'-aryl-N-arylureido group, an N',N'-diaryl-N-alkylureido group, an N',N'-diaryl-N-arylureido group, an N'-alkyl-N'-aryl-N-alkylureido group, an N'-alkyl-N'-aryl-N-arylureido group, an alkoxycarbonylamino group, an aryloxycarbonylamino group, an N-alkyl-N-alkoxycarbonylamino group, an N-alkyl-N-aryloxycarbonylamino group, an N-aryl-N-alkoxycarbonylamino group, and an N-aryl-N-aryloxycarbonylamino group. As the alkyl group and the aryl group in these substituted amino groups, the above-described alkyl groups, substituted alkyl groups, aryl groups, and substituted aryl groups can be exemplified.  $R^6$  in the acyl group ( $R^6CO-$ ) in the above acylamino group, N-alkylacylamino group and N-arylacylamino group has the same meaning as described above. Of the above-described

substituted amino groups, an N-alkylamino group, an N,N-dialkylamino group, an N-arylamino group, and an acylamino group are more preferred. The specific examples of the preferred substituted amino groups include a methylamino group, an ethylamino group, a diethylamino group, a morpholino group, a piperidino group, a pyrrolidino group, a phenylamino group, a benzoylamino group, and an acetylamino group.

**[0072]** As the substituted carbonyl groups ( $R^{11}CO-$ ), those in which  $R^{11}$  represents a monovalent non-metallic atomic group can be used. The preferred examples of the substituted carbonyl groups include a formyl group, an acyl group, a carboxyl group, an alkoxycarbonyl group, an aryloxy carbonyl group, a carbamoyl group, an N-alkylcarbamoyl group, an N,N-dialkylcarbamoyl group, an N-arylcarbamoyl group, an N,N-diarylcarbamoyl group, and an N-alkyl-N-arylcarbamoyl group. As the alkyl group and the aryl group in these substituted carbonyl groups, the above-described alkyl groups, substituted alkyl groups, aryl groups, and substituted aryl groups can be exemplified. Of the above-described substituted carbonyl groups, a formyl group, an acyl group, a carboxyl group, an alkoxycarbonyl group, an aryloxy carbonyl group, a carbamoyl group, an N-alkylcarbamoyl group, an N,N-dialkylcarbamoyl group, and an N-arylcarbamoyl group are more preferred, and a formyl group, an acyl group, an alkoxycarbonyl group, and an aryloxy carbonyl group are still more preferred. The specific examples of the preferred substituted carbonyl groups include a formyl group, an acetyl group, a benzoyl group, a carboxyl group, a methoxycarbonyl group, an allyloxy carbonyl group, an N-methylcarbamoyl group, an N-phenylcarbamoyl group, an N,N-diethylcarbamoyl group, and a morpholinocarbonyl group.

**[0073]** As the substituted sulfinyl groups ( $R^{12}SO-$ ), those in which  $R^{12}$  represents a monovalent non-metallic atomic group can be used. The preferred examples of the substituted sulfinyl groups include an alkylsulfinyl group, an arylsulfinyl group, a sulfinamoyl group, an N-alkylsulfinamoyl group, an N,N-dialkylsulfinamoyl group, an N-arylsulfinamoyl group, an N,N-diarylsulfinamoyl group, and an N-alkyl-N-arylsulfinamoyl group. As the alkyl group and the aryl group in these substituted sulfinyl groups, the above-described alkyl groups, substituted alkyl groups, aryl groups, and substituted aryl groups can be exemplified. Of the above-described substituted sulfinyl groups, an alkylsulfinyl group and an arylsulfinyl group are more preferred. The specific examples of the substituted sulfinyl groups include a hexylsulfinyl group, a benzylsulfinyl group, and a tolylsulfinyl group.

**[0074]** As the substituted sulfonyl groups ( $R^{13}SO_2-$ ), those in which  $R^{13}$  represents a monovalent non-metallic atomic group can be used. The preferred examples of the substituted sulfonyl groups include an alkylsulfonyl group and an arylsulfonyl group. As the alkyl group and the aryl group in these substituted sulfonyl groups, the above-described alkyl groups, substituted alkyl groups, aryl groups, and substituted aryl groups can be exemplified. The specific examples of the substituted sulfonyl groups include a butylsulfonyl group and a chlorophenylsulfonyl group.

**[0075]** The sulfonato group ( $-SO_3-$ ) means a conjugate base anion group of a sulfo group ( $-SO_3H$ ) as described above and, in general, they are preferably used with a counter cation. As such a counter cation, generally used various oniums (e.g., ammoniums, sulfoniums, phosphoniums, iodoniums, aziniums) and metal ions (e.g.,  $Na^+$ ,  $K^+$ ,  $Ca^{2+}$ ,  $Zn^{2+}$ ) can be exemplified.

**[0076]** The carboxylato group ( $-CO_2-$ ) means a conjugate base anion group of a carboxyl group ( $CO_2H$ ) as described above and, in general, they are preferably used with a counter cation. As such a counter cation, generally used various oniums (e.g., ammoniums, sulfoniums, phosphoniums, iodoniums, aziniums) and metal ions (e.g.,  $Na^+$ ,  $K^+$ ,  $Ca^{2+}$ ,  $Zn^{2+}$ ) can be exemplified.

**[0077]** The substituted phosphono group means a group obtained by substituting one or two hydroxyl group(s) on a phosphono group with other organic oxo group(s), and the preferred examples include the above-described dialkylphosphono group, diarylphosphono group, alkylarylphosphono group, monoalkylphosphono group and monoarylphosphono group. Of these groups, the dialkylphosphono group and the diarylphosphono group are preferred. The specific examples of these substituted phosphono groups include a diethylphosphono group, a dibutylphosphono group, and a diphenylphosphono group.

**[0078]** The phosphonato group ( $-PO_3^{2-}$ ,  $-PO_3H^-$ ) means a conjugate base anion group of a phosphono group ( $-PO_3H_2$ ) resulting from primary acid dissociation or secondary acid dissociation as described above. In general, they are preferably used with a counter cation. As such a counter cation, generally used various oniums (e.g., ammoniums, sulfoniums, phosphoniums, iodoniums, aziniums) and metal ions (e.g.,  $Na^+$ ,  $K^+$ ,  $Ca^{2+}$ ,  $Zn^{2+}$ ) can be exemplified.

**[0079]** The substituted phosphonato group is, of the above-described substituted phosphono groups, a conjugate base anion group of a group obtained by substituting one hydroxyl group with an organic oxo group, and specific examples include the conjugate base groups of the above-described monoalkylphosphono group ( $-PO_3H(alkyl)$ ) and a monoarylphosphono group ( $-PO_3H(aryl)$ ). In general, they are preferably used with a counter cation. As such a counter cation, generally used various oniums (e.g., ammoniums, sulfoniums, phosphoniums, iodoniums, aziniums) and metal ions (e.g.,  $Na^+$ ,  $K^+$ ,  $Ca^{2+}$ ,  $Zn^{2+}$ ) can be exemplified.

**[0080]** In the above formula (I), A more preferably represents an organic group containing an aromatic group, and W preferably represents a nonionic organic group containing a polyoxyalkylene group.

**[0081]** The specific examples of A-H and W-H are shown below.

Examples of A-H

[0082]

5

①

10




15

logP= 2.05

②

20




25

3.05

③

30




35

4.05

④

40




45

3.73

⑤


50



55

3.27

⑥



3.33

⑦




2.38

⑧ Straight chain or branched  $C_nH_{2n+2}$  (an integer of  $n \geq 4$ ) $\log P = 2.09$  (in the case of butane)⑨ Straight chain or branched  $C_nH_{2n}$  (an integer of  $n \geq 4$ )⑩ Straight chain or branched  $C_nH_{2n-2}$  (an integer of  $n \geq 4$ )


[0083] The above-described substituent on the hydrocarbon group may be substituted with the hydrogen atoms of the above structural formulae ① to ⑩.

Examples of W-H


[0084]

(an integer of  $n \geq 1$ ) $\log P$ 








$$\begin{cases} -0.71(n=1), -1.37(n=5) \\ -2.19(n=10), -3.02(n=15) \end{cases}$$



(an integer of  $n \geq 1$ )

$$(-0.30(n=1), 0.70(n=5))$$



(integers of  $n \geq 1, m \geq 1$ )







$\alpha$  and  $\omega$  each represents  $-\text{OH}$ ,  $-\text{H}$ ,  $-\text{SH}$  or  $-\text{NH}_2$



[0085] The above-described substituent on the hydrocarbon group may be substituted with the hydrogen atoms of the above structural formulae  $\textcircled{1}$  to  $\textcircled{14}$ .

[0086] The examples of the nonionic compounds represented by formula (I) are shown below.


## Examples of the Compounds Represented by Formula (I)

[0087]


5

A-W


10




15




20




25




30




35

(t)C<sub>4</sub>H<sub>9</sub>


40

(n)C<sub>8</sub>H<sub>17</sub>O

45

C<sub>3</sub>H<sub>7</sub>CO<sub>2</sub>

50

(CH<sub>3</sub>)<sub>2</sub>N


55

## Examples of the Compounds Represented by Formula (I)


[0088]

A-W


Y-10




Y-11




Y-12




Y-13




Y-14



Y-15



Y-16




### Examples of the Compounds Represented by Formula (I)



**[0089]**

A-W


Y-17




Y-18




Y-19




Y-20





Y-21



Y-22



**[0090]** The nonionic compound represented by formula (I) is more preferably represented by the following formula (I-A) or (I-B) :



wherein  $R_1$  and  $R_2$  each represents H or an alkyl group having from 1 to 100 carbon atoms, and  $n$  and  $m$  each represents an integer of from 0 to 100.

**[0091]** The examples of the compounds represented by formula (I-A) include polyoxyethylene phenyl ether, polyoxyethylene methylphenyl ether, polyoxyethylene octylphenyl ether, and polyoxyethylene nonylphenyl ether.

**[0092]** The examples of the compounds represented by formula (I-B) include polyoxyethylene naphthyl ether, polyoxyethylene methyl naphthyl ether, polyoxyethylene octyl naphthyl ether, and polyoxyethylene nonyl naphthyl ether.

**[0093]** In the compound represented by formula (I-A) or (I-B), the number of the repeating unit of polyoxyethylene chain is preferably from 3 to 50, more preferably from 5 to 30, and the number of the repeating unit of polyoxypropylene chain is preferably from 0 to 10, more preferably from 0 to 5. The polyoxyethylene moiety and polyoxypropylene moiety may be a random copolymer or a block copolymer.

**[0094]** The nonionic aromatic ether-based activator represented by formula (I-A) or (I-B) may be used alone or in combination of two or more.

**[0095]** Similarly to the polyoxyalkylene ethers represented by formula (I-A) or (I-B), the nonionic compound having a polyoxyalkylene ether group (i.e., a nonionic surfactant) represented by the following formula (I-C) may be used in the developing solution for use in the present invention as the preferred nonionic compound represented by formula (I).

**[0096]** As the surfactant having a polyoxyalkylene ether group, the compound represented by the following formula (I-C) is preferably used:



wherein  $R^1$  represents an alkyl group having from 3 to 15 carbon atoms which may have a substituent, an aromatic hydrocarbon group having from 6 to 15 carbon atoms which may have a substituent, or a heterocyclic aromatic group having from 4 to 15 carbon atoms which may have a substituent (as the substituents, an alkyl group having from 1 to 20 carbon atoms, a halogen atom, e.g., Br, Cl and I, an aromatic hydrocarbon group having from 6 to 15 carbon atoms, an aralkyl group having from 7 to 17 carbon atoms, an alkoxyl group having from 1 to 20 carbon atoms, an alkoxycarbonyl group having from 2 to 20 carbon atoms, and an acyl group having from 2 to 15 carbon atoms can be exemplified);  $R^2$  represents an alkylene group having from 1 to 100 carbon atoms which may have a substituent (as the substituents, an alkyl group having from 1 to 20 carbon atoms and an aromatic hydrocarbon group having from 6 to 15 carbon atoms can be exemplified); and  $n$  represents an integer of from 1 to 100.

**[0097]** The  $(\text{R}^2 - \text{O})_n$  moiety in formula (I) may be two or three groups within the above range. Specifically, random or block copolymers of a combination of an ethyleneoxy group and a propyleneoxy group, a combination of an ethyleneoxy group and an isopropyleneoxy group, a combination of an ethyleneoxy group and a butyleneoxy group, and a combination of an ethyleneoxy group and an isobutylene group can be exemplified.

**[0098]** By containing the nonionic surfactant having a polyoxyalkylene ether group in the developing solution for use in the present invention, the dissolution of the photosensitive layer in an unexposed domain is accelerated and the osmosis property of the developing solution to an exposed domain is reduced.

**[0099]** The effective addition amount of the nonionic compound represented by formula (I) is from 1 to 30 wt%, preferably from 1 to 20 wt%, more preferably from 2 to 20 wt%, and most preferably from 2 to 10 wt%, in the developing solution.

**[0100]** If the addition amount is too small, developing property and the solubility of the components of a photosensitive layer are reduced, while when it is too much, the press life (i.e., the printing durability) of a printing plate is deteriorated.

Chelating agent

[0101] The developing solution according to the present invention may contain a chelating agent. Examples of chelating agents include polyphosphate, (e.g.,  $\text{Na}_2\text{P}_2\text{O}_7$ ,  $\text{Na}_5\text{P}_3\text{O}_{10}$ ,  $\text{Na}_3\text{P}_3\text{O}_9$ ,  $\text{Na}_2\text{O}_4\text{P}(\text{NaO}_3\text{P})\text{PO}_3\text{Na}_2$ , Calgon (sodium polymetaphosphate)); aminopolycarboxylic acids, (e.g., ethylenediaminetetraacetic acid, potassium salt of it, sodium salt of it; diethylenetriaminepentaacetic acid, potassium salt of it, sodium salt of it; triethylenetetraminehexaacetic acid, potassium salt of it, sodium salt of it; hydroxyethyl ethylenediaminetriacetic acid, potassium salt of it, sodium salt of it; nitrilotriacetic acid, potassium salt of it, sodium salt of it; 1,2-diaminocyclohexanetetraacetic acid, potassium salt of it, sodium salt of it; 1,3-diamino-2-propanoltetraacetic acid, potassium salt of it, sodium salt of it); organic phosphonic acids, (e.g., 2-phosphonobutane-1,2,4-tricarboxylic acid, potassium salt of it, sodium salt of it; 2-phosphonobutanone-2,3,4-tricarboxylic acid, potassium salt of it, sodium salt of it; 1-phosphonoethane-1,2,2-tricarboxylic acid, potassium salt of it, sodium salt of it; 1-hydroxyethane-1,1-diphosphonic acid, potassium salt of it, sodium salt of it; aminotri(methylenephosphonic acid), potassium salt of it, sodium salt of it). The optimal amount of these chelating agents is various according to the hardness of the hard water to be used and the use amount of the water, but generally the amount is from 0.01 to 5 wt%, preferably from 0.01 to 0.5 wt%, in the working developing solution.

Alkali agent

[0102] The developing solution for use in the present invention is an alkaline aqueous solution containing the nonionic compound represented by formula (I). As the alkali agents to be added, inorganic alkali agents, e.g., sodium tertiary phosphate, potassium tertiary phosphate, ammonium tertiary phosphate, sodium carbonate, potassium carbonate, ammonium carbonate, sodium hydrogencarbonate, potassium hydrogencarbonate, ammonium hydrogencarbonate, sodium borate, potassium borate, ammonium borate, sodium hydroxide, potassium hydroxide, ammonium hydroxide, and lithium hydroxide, and in addition, an organic alkali agent, e.g., monomethylamine, dimethylamine, trimethylamine, monoethylamine, diethylamine, triethylamine, monoisopropylamine, diisopropylamine, triisopropylamine, n-butylamine, monoethanolamine, diethanolamine, triethanolamine, monoisopropanolamine, diisopropanolamine, ethyleneimine, ethylenediamine, pyridine, and tetramethylammonium hydroxide can be used for the purpose of delicately adjusting alkali concentration and assisting dissolution of a photosensitive layer.

[0103] These alkali agents may be used alone or two or more in combination.

Surfactant

[0104] In addition to the above nonionic compound represented by formula (I), various surfactants may be added to the developing solution for use in the present invention, as shown below.

[0105] The examples of other surfactants which can be used in the present invention include nonionic surfactants such as polyoxyethylene alkyl ethers, e.g., polyoxyethylene lauryl ether, polyoxyethylene cetyl ether, and polyoxyethylene stearyl ether, polyoxyethylene alkylaryl ethers, e.g., polyoxyethylene octylphenyl ether and polyoxyethylene nonylphenyl ether, polyoxyethylene alkyl esters, e.g., polyoxyethylene stearate, sorbitan alkyl esters, e.g., sorbitan monolaurate, sorbitan monostearate, sorbitan distearate, sorbitan monooleate, sorbitan sesquistearate, and sorbitan trioleate, and monoglyceride alkyl esters, e.g., glycerol monostearate and glycerol monooleate; anionic surfactants such as alkylbenzenesulfonates, e.g., sodium dodecylbenzenesulfonate, alkyl-naphthalenesulfonates, e.g., sodium butyl-naphthalenesulfonate, sodium pentylnaphthalenesulfonate, sodium hexylnaphthalenesulfonate, and sodium octylnaphthalenesulfonate, alkylsulfates, e.g., sodium lauryl sulfate, alkylsulfonates, e.g., sodium dodecylsulfonate, and sulfosuccinates, e.g., sodium dilaurylsulfosuccinate; and ampholytic surfactants such as alkyl betaines, e.g., lauryl betaine and stearyl betaine, and aminoacids. Of these, particularly preferred surfactants are anionic surfactants such as alkyl-naphthalenesulfonates.

[0106] These surfactants can be used alone or in combination. The content of these surfactants in a developing solution is preferably from 0.1 to 20 wt% calculated in terms of effective components.

Other components

[0107] In addition to the above-described components, if necessary, various components can be added to the developing solution for use in the present invention. For example, organic carboxylic acids, e.g., benzoic acid, phthalic acid, p-ethylbenzoic acid, p-n-propylbenzoic acid, p-isopropylbenzoic acid, p-n-butylbenzoic acid, p-t-butylbenzoic acid, p-2-hydroxyethylbenzoic acid, decanoic acid, salicylic acid and 3-hydroxy-2-naphthoic acid; organic solvents, e.g., isopropyl alcohol, benzyl alcohol, ethyl cellosolve, butyl cellosolve, phenyl cellosolve, propylene glycol, and diacetone alcohol; in addition, chelating agents, reducing agents, dyes, pigments, water softeners and antiseptics can be used.

[0108] In view of the processing stability, it is preferred that carbonic acid or carbonate be added to the developing

solution for use in the present invention. In general, the developing agent is neutralized with carbonic acid gas in the air and comes to be fatigued, but it is thought that the addition of carbonic acid or carbonate to the developing solution in advance is effective to prevent the fatigue due to carbonic acid gas from occurring by chemical equilibrium.

[0109] Further, when the printing plate of the present invention is development processed with an automatic processor, since the developing solution becomes fatigued with the processing amount, the processing ability may be restored with a replenisher or a fresh developing solution.

[0110] The properties of the developing solution are described below.

#### pH

[0111] The developing solution according to the present invention is an alkaline aqueous solution having a pH value of 12.5, preferably from 10.0 to 12.5, more preferably from 11.0 to 12.5, and particularly preferably from 11.0 to 12.0, in view of the developing speed.

[0112] If the pH value is lower than the above range, image is difficult to be formed, while if it exceeds the above range, over-development may occur or the exposed domain may be damaged severely due to development.

#### Electrical conductance

[0113] The electrical conductance of the developing solution according to the present invention is 30 mS/cm or less, preferably from 3 to 30 mS/cm, more preferably from 3 to 20 mS/cm, still more preferably from 3 to 15 mS/cm, and especially preferably from 5 to 15 mS/cm, in view of the developing speed.

[0114] If the electrical conductance exceeds the above range, since the concentration of the salt becomes high, the dissolution speed of a photosensitive layer becomes extremely slow, as a result, the residual film is liable to occur in the unexposed domain.

#### Foaming

[0115] A developing solution (30 ml) is put in a transparent glass bottle having an inner diameter of 3 cm and a capacity of 100 ml and the bottle is shaken up and down at 25°C at a rate of three times a second for one minute, and then the bottle is allowed to stand and the time until the foams disappear (time of defoaming) is measured. The smaller the time, the lower is foaming (defoaming property is high).

[0116] The developing solution according to the present invention is preferably low in foaming, time of defoaming is 5 minutes or less, and the development processing step is not interfered with by foaming at development processing.

#### Color

[0117] The developing solution according to the present invention is colorless, preferably colored slightly in a degree of capable of obtaining visibility for the purpose of preventing mistaking the developing solution for water.

#### Viscosity

[0118] The viscosity of the developing solution according to the present invention is preferably from 1.0 to 10.0 cp at 25°C in a diluted state with water, thereby the development processing progresses smooth.

#### Photosensitive lithographic printing plate

[0119] The photosensitive lithographic printing plate for use in the present invention is described below.

#### Photosensitive layer

[0120] The photosensitive layer of the photosensitive lithographic printing plate precursor according to the present invention is described in the first place.

[0121] The photosensitive layer of the photosensitive lithographic printing plate according to the present invention is not particularly restricted but it is preferably a negative type photopolymerizable photosensitive layer capable of laser imaging.

[0122] The main components of a photopolymerizable photosensitive layer comprises:

- a) a compound having an addition polymerizable ethylenically unsaturated double bond,



- b) a high polymer which is soluble or swellable in an alkaline aqueous solution (a high polymer binder),  
c) a photopolymerization initiator.

Various compounds, e.g., a colorant, a plasticizer, a thermal polymerization inhibitor, are used, if necessary.

**[0123]** The compound having an ethylenically unsaturated double bond is a compound having an ethylenically unsaturated double bond which undergoes addition polymerization, crosslinking and curing by the function of a photopolymerization initiator when the photopolymerizable photosensitive composition is irradiated with actinic radiation.

**[0124]** The compound having an addition polymerizable ethylenically unsaturated double bond can be arbitrarily selected from among the compounds having at least one, preferably two or more, ethylenically unsaturated double bonds at terminals.

**[0125]** Such compounds have, for example, the chemical form of a monomer, a prepolymer, i.e., a dimer, a trimer, and an oligomer or a mixture and a copolymer of them.

**[0126]** As examples of monomers and copolymers of them, esters of unsaturated carboxylic acids (e.g., acrylic acid, methacrylic acid, itaconic acid, crotonic acid, isocrotonic acid, maleic acid, etc.), and aliphatic polyhydric alcohol compounds, and amides of unsaturated carboxylic acids and aliphatic polyhydric amine compounds are exemplified.

**[0127]** Specific examples of ester monomers of aliphatic polyhydric alcohol compounds and unsaturated carboxylic acids include, as acrylates, ethylene glycol diacrylate, triethylene glycol diacrylate, 1,3-butanediol diacrylate, tetramethylene glycol diacrylate, propylene glycol diacrylate, neopentyl glycol diacrylate, trimethylolpropane triacrylate, trimethylolpropane tri(acryloyloxypropyl) ether, trimethylolethane triacrylate, hexanediol diacrylate, 1,4-cyclohexanediol diacrylate, tetraethylene glycol diacrylate, pentaerythritol diacrylate, pentaerythritol triacrylate, pentaerythritol tetraacrylate, dipentaerythritol diacrylate, dipentaerythritol pentaacrylate, dipentaerythritol hexaacrylate, sorbitol triacrylate, sorbitol tetraacrylate, sorbitol pentaacrylate, sorbitol hexaacrylate, tri(acryloyloxyethyl) isocyanurate, polyester acrylate oligomer, etc.

**[0128]** As methacrylates, examples include tetramethylene glycol dimethacrylate, triethylene glycol dimethacrylate, neopentyl glycol dimethacrylate, trimethylolpropane trimethacrylate, trimethylolethane trimethacrylate, ethylene glycol dimethacrylate, 1,3-butanediol dimethacrylate, hexanediol dimethacrylate, pentaerythritol dimethacrylate, pentaerythritol trimethacrylate, pentaerythritol tetramethacrylate, dipentaerythritol dimethacrylate, dipentaerythritol hexamethacrylate, dipentaerythritol pentamethacrylate, sorbitol trimethacrylate, sorbitol tetramethacrylate, bis[p-(3-methacryloxy-2-hydroxypropoxy)phenyl]dimethylmethane, bis[p-(methacryloxyethoxy)phenyl]dimethylmethane, etc.

**[0129]** As itaconates, examples include ethylene glycol diitaconate, propylene glycol diitaconate, 1,3-butanediol diitaconate, 1,4-butanediol diitaconate, tetramethylene glycol diitaconate, pentaerythritol diitaconate, sorbitol tetraitaconate, etc.

**[0130]** As crotonates, examples include ethylene glycol dicrotonate, tetramethylene glycol dicrotonate, pentaerythritol dicrotonate, sorbitol tetradicrotonate, etc.

**[0131]** As isocrotonates, examples include ethylene glycol diisocrotonate, pentaerythritol diisocrotonate, sorbitol tetraisocrotonate, etc.

**[0132]** As maleates, examples include ethylene glycol dimaleate, triethylene glycol dimaleate, pentaerythritol dimaleate, sorbitol tetramaleate, etc.

**[0133]** Further, the mixtures of the above-described ester monomers can also be exemplified.

**[0134]** Further, specific examples of amide monomers of aliphatic polyhydric amine compounds and unsaturated carboxylic acids include methylenebis-acrylamide, methylene-bis-methacrylamide, 1,6-hexamethylenebis-acrylamide, 1,6-hexamethylenebis-methacrylamide, diethylenetriaminetris-acrylamide, xylylenebis-acrylamide, xylylenebis-methacrylamide, etc.

**[0135]** As other example, as is disclosed in JP-B-48-41708 (the term "JP-B" as used herein means an "examined Japanese patent publication"), a vinyl urethane compound having two or more polymerizable vinyl groups in one molecule can be exemplified, which is obtained by the addition of a vinyl monomer having a hydroxyl group represented by the following formula (A) to a polyisocyanate compound having two or more isocyanate groups in one molecule can be exemplified.



wherein  $\text{R}_3$  and  $\text{R}_4$  each represents H or  $\text{CH}_3$ .

**[0136]** As other examples, urethane acrylates as disclosed in JP-A-51-37193 and JP-B-2-32293, polyfunctional acrylates and methacrylates, such as polyester acrylates, and epoxy acrylates obtained by reacting epoxy resins with (meth)acrylic acids as disclosed in JP-A-48-64183, JP-B-49-43191 and JP-B-52-30490 can be exemplified. Moreover, photo-curable monomers and oligomers introduced into Bulletin of Nihon Setchaku Kyokai, Vol. 20, No. 7, pp. 300-308

(1984) can be used as well. The use amount of these ethylenically unsaturated compounds is generally from 5 to 80 wt%, preferably from 5 to 70 wt%, more preferably from 10 to 70 wt%, and most preferably from 30 to 50 wt%, based on the total components (hereinafter, wt% is abbreviated merely to %).

**[0137]** The high polymers soluble or swellable in alkali water which are used in the photosensitive layer of the photosensitive lithographic printing plate according to the present invention are selected not only as a film-forming agent of the composition of the photosensitive layer but according to the use of the alkali developing agent. For example, when water-soluble organic high polymers are used, water development becomes possible. As such organic high polymers, addition polymers having a carboxylic acid group at the side chain, e.g., the polymers disclosed in JP-A-59-44615, JP-B-54-34327, JP-B-58-12577, JP-B-54-25957, JP-A-54-92723, JP-A-59-53836 and JP-A-59-71048, i.e., a methacrylic acid copolymer, an acrylic acid copolymer, an itaconic acid copolymer, a crotonic acid copolymer, a maleic acid copolymer, and a partially esterified maleic acid copolymer, can be exemplified.

**[0138]** Acidic cellulose derivatives having a carboxylic acid group at the side chain can also be used. Besides the above, the polymers obtained by adding a cyclic acid anhydride to an addition polymer having a hydroxyl group are also useful. Of these polymers, in particular, copolymers of [benzyl (meth)acrylate-(meth)acrylic acid-other addition polymerizable vinyl monomer according to necessity] and [allyl (meth)acrylate-(meth)acrylic acid-other addition polymerizable vinyl monomer according to necessity] are advantageously used in the present invention. Further, as water-soluble organic polymers, polyvinyl pyrrolidone and polyethylene oxide are useful. For increasing the strength of cured films, alcohol-soluble polyamide and polyether of 2,2-bis(4-hydroxyphenyl)propane and epichlorohydrin are also useful.

**[0139]** The urethane resins disclosed in JP-B-7-120040, JP-B-7-120041, JP-B-7-120042, JP-B-8-12424, JP-A-63-287944, JP-A-63-287947, JP-A-1-271741, and JP-A-11-352691 are also useful for the use of the present invention.

**[0140]** By introducing radical reactive groups into the side chain of these high polymers, the strength of the cured film can be improved. A group having an ethylenically unsaturated bond, an amino group and an epoxy group can be exemplified as an addition polymerization reactive functional group, a mercapto group, a thiol group, a halogen atom, a triazine structure and an onium structure can be exemplified as a functional group capable of becoming a radical by irradiation, and a carboxyl group and an imido group can be exemplified as a polar group. As the above addition polymerization reactive functional group, a group having an ethylenically unsaturated bond, e.g., an acryl group, a methacryl group, an allyl group, and a styrene group, is particularly preferred, but functional groups selected from among an amino group, a hydroxyl group, a phosphonic acid group, a phosphoric acid group, a carbamoyl group, an isocyanate group, a ureido group, a ureylene group, a sulfonic acid group and an ammonio group are also useful.

**[0141]** For maintaining the developing properties of the composition, it is preferred that the high polymer of the present invention should have an appropriate molecular weight and an acid value. It is preferred to use a high polymer (binder) having a weight average molecular weight of from 5,000 to 300,000 and an acid value of from 0.2 to 5.0 meq/g to be processed with the above-described developing solution.

**[0142]** For maintaining the developing properties of the composition, it is preferred that the high polymer (binder) of the present invention should have an appropriate molecular weight and an acid value, e.g., a high polymer having a weight average molecular weight of from 5,000 to 300,000 and an acid value of from 20 to 200 is effectively used.

**[0143]** These organic high polymers can be mixed in the entire composition of the photosensitive layer in an arbitrary amount. If the amount exceeds 90 wt%, sufficient image strength cannot be obtained. The amount is preferably from 10 to 90 wt%, more preferably from 30 to 80 wt%. It is preferred that the ratio of the photopolymerizable ethylenically unsaturated compound to the organic high polymer be from 1/9 to 9/1, more preferably from 2/8 to 8/2, and still more preferably from 3/7 to 7/3, by weight.

**[0144]** As the photopolymerizable initiators for use in the photosensitive layer of the photosensitive lithographic printing plate according to the present invention, various kinds of photopolymerization initiator well-known by patents and literature can be used arbitrarily according to the wavelength of the light sources to be used. These photopolymerization initiators may be used in combination of two or more.

**[0145]** When a visible light of 400 nm or more, an Ar laser, a second harmonic wave of a semiconductor laser, or an SHG-YAG laser is used as a light source, various photopolymerization initiators are suggested. For example, a certain kind of photoreducing dyes as disclosed in U.S. Patent 2,850,445, e.g., Rose Bengale, Eosine and Erythrosine, or series comprising a combination of a dye and a photopolymerization initiator, e.g., a composite initiator comprising a dye and an amine (JP-B-44-20189), series comprising a combination of a hexaarylbiimidazole, a radical generator and a dye (JP-B-45-37377), series comprising a hexaarylbiimidazole and a p-dialkylaminobenzylidene ketone (JP-B-47-2528, JP-A-54-155292), series comprising a cyclic cis- $\alpha$ -dicarbonyl compound and a dye (JP-A-48-84183), series comprising a cyclic triazine and a merocyanine dye (JP-A-54-151024), series comprising a 3-ketocoumarin and an activator (JP-A-52-112681, JP-A-58-15503), series comprising a biimidazole, a styrene derivative and a thiol (JP-A-59-140203), series comprising an organic peroxide and a dye (JP-A-59-1504, JP-A-59-140203, JP-A-59-189340, JP-A-62-174203, JP-B-62-1641, U.S. Patent 4,766,055), series comprising a dye and an active halogen compound (JP-A-63-258903, JP-A-2-63054), series comprising a dye and a borate compound (JP-A-62-143044, JP-A-62-150242, JP-A-64-13140, JP-A-64-13141, JP-A-64-13142, JP-A-64-13143, JP-A-64-13144, JP-A-64-17048, JP-A-1-229003,

JP-A-1-298348, JP-A-1-138204), series comprising a dye having a rhodanine ring and a radical generator (JP-A-2-179643, JP-A-2-244050), series comprising a titanocene and a 3-ketocoumarin dye (JP-A-63-221110), series comprising a combination of a titanocene, a xanthene dye, and an addition polymerizable ethylenically unsaturated compound having an amino group or a urethane group (JP-A-4-221958, JP-A-4-219756), series comprising a titanocene and a specific merocyanine dye (JP-A-6-295061), and series comprising a titanocene and a dye having a benzopyran ring (JP-A-8-334897) can be exemplified.

[0146] In recent years, a laser having wavelength of from 400 to 410 nm (a violet laser) has been developed and photopolymerization initiators having high sensitivity to the wavelength of 450 nm or lower sensitive to this laser have been developed, and these photopolymerization initiators can also be used in the present invention.

[0147] For example, a cationic dye/borate series (JP-A-11-84647), a merocyanine dye/titanocene series (JP-A-2000-147763), and a carbazole type dye/titanocene series (JP-A-2001-42524) can be exemplified.

[0148] In the present invention, the series in which a titanocene compound is used is particularly excellent in view of sensitivity and preferred.

[0149] Various kinds of titanocene compounds can be used, e.g., the titanocene compounds disclosed in JP-A-59-152396 and JP-A-61-151197 can be arbitrarily used. More specifically, dicyclopentadienyl-Ti-dichloride, dicyclopentadienyl-Ti-bisphenyl, dicyclopentadienyl-Ti-bis-2,3,4,5,6-pentafluorophen-1-yl, dicyclopentadienyl-Ti-bis-2,3,5,6-tetrafluorophen-1-yl, dicyclopentadienyl-Ti-bis-2,4,6-trifluorophen-1-yl, dicyclopentadienyl-Ti-bis-2,6-difluorophen-1-yl, dicyclopentadienyl-Ti-bis-2,4-difluorophen-1-yl, dimethylcyclopentadienyl-Ti-bis-2,3,4,5,6-pentafluorophen-1-yl, dimethylcyclopentadienyl-Ti-bis-2,6-difluorophen-1-yl, dicyclopentadienyl-Ti-bis-2,6-difluoro-3-(pir-1-yl)phen-1-yl can be exemplified.

[0150] It is known that by adding hydrogen-donating compounds, such as thiol compounds, e.g., 2-mercaptobenzo-thiazole, 2-mercaptobenzimidazole, and 2-mercaptobenzoxazole, and amine compounds, e.g., N-phenylglycine and N,N-dialkylamino aromatic alkyl ester to the above photopolymerization initiators, if necessary, photopolymerization initiating property is further improved.

[0151] The auxiliary agents such as amine compounds and thiol compounds may be added to the photopolymerization initiators, if necessary. By the addition of these hydrogen-donating compounds, photopolymerization initiating property can be further improved.

[0152] The addition amount of these photopolymerization initiators is from 0.05 to 100 weight parts, preferably from 0.1 to 70 weight parts, and more preferably from 0.2 to 50 weight parts, per 100 weight parts of the ethylenically unsaturated compound.

[0153] Besides the above main components, it is preferred for the photosensitive composition for the photosensitive layer according to the present invention to contain a small amount of thermal polymerization inhibitor for inhibiting unnecessary thermal polymerization of an ethylenically unsaturated compound during production or storage. As the appropriate thermal polymerization inhibitors, hydroquinone, p-methoxyphenol, di-t-butyl-p-cresol, pyrogallol, t-butylcatechol, benzoquinone, 4,4'-thiobis(3-methyl-6-t-butylphenol), 2,2'-methylene-bis(4-methyl-6-t-butylphenol), N-nitrosophenylhydroxylamine primary cerium salt, and N-nitrosophenylhydroxylamine aluminum salt can be exemplified. The addition amount of the thermal polymerization inhibitor is preferably from about 0.01% to about 5% based on the weight of the entire composition. Further, if necessary, higher fatty acid derivatives, such as behenic acid and behenic acid amide, may be added to the photosensitive composition of the photosensitive layer and localized on the surface of the photosensitive layer during drying process after coating to inhibit polymerization hindrance due to oxygen. The addition amount of the higher fatty acid derivative is preferably from about 0.5% to about 10% based on the entire composition.

[0154] Colorants may be added for the purpose of coloring the photosensitive layer. As the colorants, pigments, e.g., phthalocyanine pigments (C.I. Pigment Blue 15/3, 15/4, 15/6), azo pigments, carbon black and titanium oxide, and dyes such as Ethyl Violet, Crystal Violet, azo dyes, anthraquinone dyes and cyanine dyes can be used. The addition amount of the dye and the pigment is preferably from about 0.5% to about 5% based on the entire composition.

[0155] In addition, for improving the physical properties of the cured film, inorganic fillers and plasticizers, e.g., dioctyl phthalate, dimethyl phthalate and tricresyl phosphate may be added.

[0156] The addition amount of these compounds is preferably 10% or less based on the entire solid content of the photosensitive layer.

[0157] When the photosensitive layer is coated on a support, which is described later, the photosensitive composition of the photosensitive layer is dissolved in various organic solvents before use. Examples of the solvents used here include acetone, methyl ethyl ketone, cyclohexane, ethyl acetate, ethylene dichloride, tetrahydrofuran, toluene, ethylene glycol monomethyl ether, ethylene glycol monoethyl ether, ethylene glycol dimethyl ether, propylene glycol monomethyl ether, propylene glycol monoethyl ether, acetylacetone, cyclohexanone, diacetone alcohol, ethylene glycol monomethyl ether acetate, ethylene glycol ethyl ether acetate, ethylene glycol monoisopropyl ether, ethylene glycol monobutyl ether acetate, 3-methoxypropanol, methoxymethoxyethanol, diethylene glycol monomethyl ether, diethylene glycol monoethyl ether, diethylene glycol dimethyl ether, diethylene glycol diethyl ether, propylene glycol mono-

methyl ether acetate, propylene glycol monoethyl ether acetate, 3-methoxypropyl acetate, N,N-dimethylformamide, dimethyl sulfoxide,  $\gamma$ -butyrolactone, methyl lactate, ethyl lactate, etc. These solvents may be used alone or may be used as a mixed solvent. The concentration of the solid content in the coating solution is preferably from 1 to 50%.

[0158] Surfactants can be added to the photopolymerizable photosensitive layer composition for the purpose of improving the properties of the coated surface.

[0159] The dry coating amount of the surfactant is preferably from about 0.1 to about 10 g/m<sup>2</sup>, more preferably from 0.3 to 5 g/m<sup>2</sup>, and still more preferably from 0.5 to 3 g/m<sup>2</sup>.

#### Acid value of photosensitive layer

[0160] The acid value of the photosensitive layer used in the present invention is the equivalent of the acids having pKa of 9 or less contained per g of the layers of the photosensitive composition coated on the support (an overcoat layer coated on the photosensitive layer, e.g., an oxygen-barrier layer is not included) of a photosensitive lithographic printing plate. Acid value of photosensitive layer can be obtained experimentally by titrating the photosensitive layer directly by an aqueous solution of sodium hydroxide, alternatively the acid value of the photosensitive layer can be computed from the content of the compounds having acid radicals having a pKa of 9 or less in the photosensitive composition.

[0161] As the specific method of changing the photosensitive layer acid value, there are methods of changing the ratio of the contents of the components of the photosensitive layer, i.e., crosslinking monomer/binder polymer having acid radicals (linear high polymer), and using binder polymers of low acid value having less acid radicals.

[0162] As the binder polymers of low acid value, the acid value is preferably 1.5 meq/g or less, more preferably 1.2 meq/g or less.

[0163] The photosensitive layer acid value of the photosensitive layer according to the present invention is preferably 1.0 meq/g. It is more effective that the present invention is applied to the lithographic printing plate having a photosensitive layer having the acid value of from 0.20 to 0.60 meq/g, more preferably from 0.30 to 0.50 meq/g, in view of image-forming properties.

#### Support

[0164] The support of the photosensitive lithographic printing plate for use in the present invention is not particularly limited so long as it is a plate-like support having dimensional stability but aluminum support is preferably used.

[0165] The aluminum support is selected from aluminum containing dimensionally stable aluminum as a main component, aluminum-containing alloys (e.g., alloys of aluminum and silicon, copper, manganese, magnesium, chromium, zinc, lead, bismuth, nickel, etc.), plastic films or paper laminated or deposited with aluminum or aluminum alloy. A composite sheet comprising a polyethylene terephthalate film having provided thereon an aluminum sheet as disclosed in JP-B-48-18327 is also preferred. The aluminum support is arbitrarily subjected to the later-described surface treatment. The aluminum supports for use in the present invention have a thickness of from about 0.05 to about 1 mm.

#### Graining treatment

[0166] The techniques of graining the surface of aluminum disclosed in JP-A-56-28893, such as mechanical surface roughening, chemical etching, and electrolytic graining are used in the present invention. Further, an electrochemical method of performing surface graining in an electrolytic solution of hydrochloric acid or nitric acid, and a mechanical method such as a wire brush graining method of scratching the aluminum surface with metal wire, a ball graining method of graining the aluminum surface with an abrading ball and an abrasive, and a brush graining method of graining the aluminum surface with a nylon brush and an abrasive can be used. These graining methods can be used alone or combination of two or more.

[0167] Of the above methods, a surface roughening method due to an electrochemical method of performing the surface graining in an electrolytic solution of hydrochloric acid or nitric acid is preferably used in the present invention. The electric current density is generally from 100 C/dm<sup>2</sup> to 400 C/dm<sup>2</sup>. More specifically, it is preferred that electrolysis is carried out in an electrolytic solution containing from 0.1 to 50% of hydrochloric acid or nitric acid at 20 to 100°C for 1 second to 30 minutes by the electric current density of from 100 to 400 C/dm<sup>2</sup>.

[0168] The aluminum support having been subjected to surface graining treatment is then subjected to chemical etching using an acid or an alkali. When an acid is used as the etching agent, time is taken for destroying minute structure and industrially disadvantageous in the present invention, but an alkali is preferably used as the etching agent.

[0169] Alkali agents preferably used in the present invention include sodium hydroxide, sodium carbonate, sodium aluminate, sodium metasilicate, sodium phosphate, potassium hydroxide and lithium hydroxide. The preferred conditions of alkali etching are such that the concentration and the temperature are from 1 to 50 wt% and from 20 to 100°C

respectively, and the solution amount of Al is from 5 to 20 g/m<sup>3</sup>.

[0170] Acid cleaning is performed for removing the smut remaining on the surface of the support after etching. The acids used are nitric acid, sulfuric acid, phosphoric acid, chromic acid, hydrofluoric acid and borofluoric acid. In particular, as the desmutting method after electrochemical surface roughening treatment, a method of bringing the aluminum support into contact with a 15 to 65 wt% solution of sulfuric acid at 50 to 90°C as disclosed in JP-A-53-12739, and a method of performing alkali etching as disclosed in JP-B-48-28123 can be exemplified.

[0171] The surface roughness (Ra) of the aluminum support preferably used in the present invention is from 0.3 to 0.7 μm.

#### 10 Anodizing treatment

[0172] The thus surface-treated aluminum support is then subjected to anodizing treatment.

[0173] Anodizing treatment can be performed by the methods so far been used in this industry. Specifically, anodizing treatment is carried out by applying an alternating or direct electric current to an aluminum support in an electrolytic solution comprising alone or combination of two or more of an aqueous solution or nonaqueous solution of sulfuric acid, phosphoric acid, chromic acid, oxalic acid, sulfamic acid, benzenesulfonic acid, to thereby form an anodic oxidation layer (or film) on the surface of the aluminum support.

[0174] The conditions of anodizing treatment vary widely according to the electrolytic solution to be used so that the conditions cannot be determined unconditionally but, in general, the concentration of an electrolytic solution is from 1 to 80 wt%, the temperature is from 5 to 70°C, the electric current density is from 0.5 to 60 A/dm<sup>2</sup>, voltage is from 1 to 100 V, and the electrolytic time is from 10 to 100 seconds.

[0175] Of these anodizing treatments, the method of performing anodizing in a sulfuric acid solution with high electric current density as disclosed in British Patent 1,412,768, and a method of performing anodizing using a phosphoric acid as the electrolytic bath as disclosed in U.S. Patent 3,511,661 are preferably used in the present invention.

[0176] In the present invention, the thickness of an anodic oxide film is preferably from 1 to 10 g/m<sup>2</sup>. When the thickness is 1 g/m<sup>2</sup> or less, the printing plate is liable to be scratched, while when it is 10 g/m<sup>2</sup> or more, a large quantity of electric power is required, thus uneconomical. The thickness is preferably from 1.5 to 7 g/m<sup>2</sup>, more preferably from 2 to 5 g/m<sup>2</sup>.

[0177] The aluminum support having been subjected to graining treatment and anodizing treatment may undergo sealing treatment. Such sealing treatment is performed by immersing the aluminum support in hot water and a hot aqueous solution containing an inorganic or organic salt and a water vapor bath. Further, at this time, the aluminum support may be subjected to surface treatment other than silicate treatment by alkali metal silicate, e.g., immersion in an aqueous solution of potassium fluoroaluminum silicate or phosphate.

[0178] Further, besides the aluminum support, plate-like materials having dimensional stability are also preferably used as the support of the photosensitive lithographic printing plate of the present invention, e.g., paper, paper laminated with plastics (e.g., polyethylene, polypropylene, polystyrene, etc.), a metal plate (e.g., zinc, copper, etc.), a plastic film (e.g., cellulose diacetate, cellulose triacetate, cellulose propionate, cellulose butyrate, cellulose acetate butyrate, cellulose nitrate, polyethylene terephthalate, polyethylene, polystyrene, polypropylene, polycarbonate, polyvinyl acetal, etc.), and paper or a plastic film laminated or deposited with the above metals can be exemplified.

[0179] Further, it is also preferred to perform surface-hydrophilizing treatment in accordance with that support. As such surface-hydrophilizing treatment, treatment by chemical reaction such as etching, oxidizing, reduction and sol-gel coating, and coating of a specific compound which adsorbs onto the surface of the support can be exemplified.

[0180] For example, in the case of an anodized aluminum support, organic compounds particularly having phosphorus series acid atomic groups (e.g., phosphoric acid, phosphonic acid, phosphinic acid) are preferably used.

[0181] The photosensitive lithographic printing plate according to the present invention is manufactured by forming the above-described photosensitive layer on the above support. Before coating a photosensitive layer, an organic or inorganic undercoat layer may be provided, if necessary.

#### 50 Oxygen barrier protective layer

[0182] The photosensitive lithographic printing plate according to the present invention may have an oxygen barrier protective layer comprising a water-soluble vinyl polymer as a main component on the photopolymerizable photosensitive layer.

[0183] As the water-soluble vinyl polymers contained in the oxygen barrier protective layer, polyvinyl alcohol, and its partial ester, ether, and acetal, and its copolymer containing unsubstituted vinyl alcohol unit of a substantial amount capable of imparting necessary water solubility can be used. Polyvinyl alcohols hydrolyzed from 71 to 100% and have a polymerization degree of from 300 to 2,400 are preferably used. Specifically, PVA-105, PVA-110, PVA-117, PVA-117H, PVA-120, PVA-124, PVA-124H, PVA-CS, PVA-CST, PVA-HC, PVA-203, PVA-204, PVA-205, PVA-210, PVA-217,

PVA-220, PVA-224, PVA-217EE, PVA-220, PVA-224, PVA-217EE, PVA-217E, PVA-220E, PVA-224E, PVA-405, PVA-420, PVA-613, and L-8 (manufactured by Kuraray Co., Ltd.) can be exemplified. As the above copolymers, polyvinyl acetate, chloroacetate, propionate, polyvinyl formal, and polyvinyl acetal hydrolyzed from 88 to 100%, and copolymers of them can be used. Other useful copolymers are polyvinyl pyrrolidone, gelatin and gum arabic, and they can be used alone or in combination.

[0184] As the solvent for coating the oxygen barrier protective layer of the present invention, pure water is preferably used, but alcohols such as methanol and ethanol, and ketones such as acetone, methyl ethyl ketone may be mixed with pure water. The concentration of the solid content in the coating solution is preferably from 1 to 20 wt%.

[0185] Well-known additives such as a surfactant for improving the coating property, and a water-soluble plasticizer for improving physical properties of the film may be added to the oxygen barrier protective layer of the present invention.

[0186] Examples of water-soluble plasticizers include, e.g., propionamide, cyclohexanediol, glycerin, sorbitol, etc. Water-soluble (meth)acrylate series polymers may be used as well.

[0187] The covering amount of the oxygen barrier protective layer is preferably about  $0.1/\text{m}^2$  to about  $15/\text{m}^2$ , more preferably from  $1.0/\text{m}^2$  to about  $5.0/\text{m}^2$ , by dry weight.

#### Plate-making process

[0188] In the plate-making process of a photosensitive lithographic printing plate, if necessary, the plate may be heated all over the surface before exposure, during exposure and from exposure to development. The image-forming reaction in the photosensitive layer is accelerated by heating, which leads to the improvement of sensitivity and press life and the stabilization of sensitivity. Further, for the purpose of improving the image strength and press life, it is effective for the image after development to be subjected to whole image post-heating or whole image exposure. The heating before development is generally preferably performed on moderate condition of  $150^\circ\text{C}$  or lower. If the temperature is too high, a problem that the non-image is fogged occurs. Heating after development is performed on very severe condition, i.e., generally from  $200$  to  $500^\circ\text{C}$ . Lower temperature does not result in sufficient image strengthening effect, while higher temperature leads to the degradation of a support and thermal decomposition of an image part.

[0189] The photosensitive lithographic printing plate of the present invention can be exposed by well-known methods with no limitation. Lasers are preferred as light sources, e.g., as available laser light sources of from 350 nm to 600 nm (preferably from 350 nm to 450 nm), the following can be used. As gas lasers: Ar ion laser (364 nm, 351 nm, 10 mW to 1 W), Kr ion laser (356 nm, 351 nm, 10 mW to 1 W), He-Cd laser (441 nm, 325 nm, 1 mW to 100 mW), As solid state lasers: a combination of 2 times of Nd:YAG ( $\text{YVO}_4$ ) and SHG crystals (355 nm, 5 mW to 1 W), a combination of Cr:LiSAF and SHG crystals (430 nm, 10 mW).

As semiconductor lasers:  $\text{KNbO}_3$  ring resonator (430 nm, 30 mW), a combination of waveguide type wavelength converting device and AlGaAs, InGaAs semiconductor (380 nm to 450 nm, 5 mW to 100 mW), a combination of waveguide type wavelength converting device and AlGaInP, AlGaAs semiconductor (300 nm to 350 nm, 5 mW to 100 mW); AlGaInN (350 nm to 450 nm, 5 mW to 30 mW), and

As other pulse lasers:  $\text{N}_2$  laser (337 nm, pulse 0.1 to 10 mJ), XeF (351 nm, pulse 10 to 250 mJ).

[0190] Of these, AlGaInN semiconductor laser (commercially available InGaN series semiconductor laser, 400 to 410 nm, 5 to 30 mW) is particularly preferred in view of the wavelength characteristics and the cost.

[0191] Besides the above, as available laser light sources of from 450 nm to 700 nm, Ar<sup>+</sup> laser (488 nm), YAG-SHG laser (532 nm), He-Ne laser (633 nm), He-Cd laser, and red semiconductor laser (from 650 to 690 nm); and as available laser light sources of from 700 nm to 1,200 nm, semiconductor laser (from 800 to 850 nm), Nd-YAG laser (1,064 nm), and FD-YAG laser can be very preferably used.

[0192] As other exposure rays, a mercury lamp of ultra-high pressure, high pressure, intermediate pressure and low pressure, a chemical lamp, a carbon arc lamp, a xenon lamp, a metal halide lamp, and various ultraviolet laser lamps (e.g., ArF excimer laser, KrF excimer laser, etc.), a halogen lamp, a fluorescent lamp, a tungsten lamp, and as radiation, electron rays, X-rays, ion beams, far infrared rays can also be used. The above laser light sources of 350 nm or more are particularly preferred in the point of inexpensiveness.

[0193] The exposure apparatuses may be any type of an internal drum type, an external drum type, or a flat bed type. By using highly water-soluble components in the photosensitive layer of the photosensitive lithographic printing plate of the present invention, the printing plate can be made soluble in neutral water or weak alkaline aqueous solution, but at the same time, the printing plate can be subjected to on-press exposure and development after mounted on a lithographic printing machine.

[0194] For the purpose of increasing the curing rate of the photopolymerizable photosensitive layer, a heating step of from  $50^\circ\text{C}$  to  $150^\circ\text{C}$  for 1 second to 5 minutes may be provided during the period after image exposure until development.

[0195] As described above, an overcoat layer having oxygen barrier properties is generally provided on the photosensitive layer of the photosensitive lithographic printing plate of the present invention. The removal of the overcoat

layer and the unexposed domain of the photosensitive layer may be performed by the developing solution of the present invention at the same time, or the overcoat layer may be removed first with water or warm water and then the unexposed domain of the photosensitive layer may be removed. The antiseptics as disclosed in JP-A-10-10754 and the organic solvents as disclosed in JP-A-8-278636 may be added to these water and warm water.

[0196] The development of the photosensitive lithographic printing plate of the present invention with the above developing solution is performed according to ordinary method at temperature of from 0 to 60°, preferably from 15 to 40°C in a manner that the exposure processed photosensitive lithographic printing plate is immersed in the developing solution and rubbed with a brush.

[0197] Further, when development processing is performed with an automatic processor, since the developing solution becomes fatigued with the processing amount, the processing ability may be restored with a replenisher or a fresh developing solution.

[0198] The thus development processed photosensitive lithographic printing plate is post-processed with washing water, a rinsing solution containing a surfactant, and a desensitizing solution containing gum arabic and a starch derivative as disclosed in JP-A-54-8002, JP-A-55-115045 and JP-A-59-58431. These processes may be used in the post-processing of the photosensitive lithographic printing plate of the present invention in various combinations.

[0199] The press life of the printing plate obtained through various processes as described above can be improved by post-exposure process and heating process such as burning according to the method as disclosed in JP-A-2000-89478.

[0200] The lithographic printing plate obtained through these processes is loaded on an offset printing machine and used for printing a lot of sheets.

### EXAMPLE

[0201] The present invention is explained in more detail with reference to the following examples, but the present invention should not be construed as being limited thereto.

### Support

#### Support 1: Anodized aluminum support

[0202] A 1S aluminum plate having a thickness of 0.30 mm was subjected to brush-graining treatment using a No. 8 nylon brush and a suspension of 800 mesh pumice stone and water, and the surface of the plate was thoroughly washed with water. The etching was effected by immersing the plate in a 10% sodium hydroxide aqueous solution at 70°C for 60 seconds, the plate was further washed with flowing water, then washed with a 20% HNO<sub>3</sub> aqueous solution for neutralization followed by washing with water. Under the condition of V<sub>A</sub> of 12.7 V using alternating waveform electric current of sine wave, the plate was subjected to electrolytic surface roughening treatment in a 1% nitric acid aqueous solution by the quantity of electricity of 300 C/dm<sup>2</sup> at anode. The surface roughness measured was 0.45 μm (Ra). Subsequently, the plate was immersed in a 30% H<sub>2</sub>SO<sub>4</sub> aqueous solution and desmutting treatment was performed at 55°C for 2 minutes. Then, the cathode was arranged on the surface having been subjected to graining treatment in a 20% H<sub>2</sub>SO<sub>4</sub> aqueous solution at 33°C, and the plate was anodized at electric current density of 5A/dm<sup>2</sup> for 50 seconds. The anodic oxidation layer obtained had a thickness of 2.7 g/m<sup>2</sup>. This plate was designated support 1.

#### Support 2

[0203] The following liquid composition 1 for undercoating for surface treatment was coated on support 1 so that the coating amount of P became about 0.05 g/m<sup>2</sup> and the support was dried at 100°C for 1 minute. The thus-obtained support was designated support 2.

#### Liquid composition 1 for undercoating

##### [0204]

Phenylphosphonic acid	2 weight parts
Methanol	800 weight parts
Water	50 weight parts



Support 3

[0205] The following liquid composition 2 for undercoating for surface treatment was coated on support 1 so that the coating amount of Si became about 0.001 g/m<sup>2</sup> and the support was dried at 100°C for 1 minute. The thus-obtained support was designated support 3.

Liquid composition 2 for undercoating

[0206] The following composition was mixed and stirred, heat generation was observed after about 5 minutes. After the reaction was continued for 60 minutes, the content was poured into different vessel, 30,000 weight parts of methanol was further added thereto, the thus obtained solution was designated liquid composition 2.

Phosmer PE (manufactured by Uni Chemical Co. Ltd.)	20 weight parts
Methanol	130 weight parts
Water	20 weight parts
Paratoluenesulfonic acid	5 weight parts
Tetraethoxysilane	50 weight parts
3-Methacryloxypropyl triethoxysilane	50 weight parts

Photosensitive material

[0207] Photopolymerizable composition shown below was coated on each of the above supports 1, 2 and 3 in a dry coating weight of 1.5 g/m<sup>2</sup>, and the coated layer was dried at 100°C for 1 minute, thereby a photosensitive layer was obtained.

[0208] A 3 wt% aqueous solution of polyvinyl alcohol (saponification degree: 98 mol%, polymerization degree: 500) was coated on the photosensitive layer in a dry coating weight of 2.5 g/m<sup>2</sup>, and dried at 100°C for 3 minutes. Thus, a photosensitive lithographic printing plate (photosensitive material) was obtained.

Coating solution for photosensitive layer


[0209] (photopolymerizable composition, details are shown in Table 1 below).

Compound (A) having ethylenically unsaturated bond	a weight parts
Linear organic high polymer (B)	b weight parts
Sensitizer (C)	0.15 weight part
Photopolymerization initiator (D)	0.30 weight part
Additive (S)	0.50 weight part
Fluorine-containing surfactant (Megafac F-177, manufactured by Dai-Nippon Ink & Chemicals, Inc.)	0.03 weight part
Thermal polymerization inhibitor (N-nitrosophenylhydroxylamine aluminum salt)	0.01 weight part
ε type copper phthalocyanine dispersion	0.2 weight part
Methyl ethyl ketone	30.0 weight parts
Propylene glycol monomethyl ether	30.0 weight parts


[0210] Compound (A) having ethylenically unsaturated bond, linear organic high polymer (B), sensitizer (C), photopolymerization initiator (D) and additive (S) for use in the coating solution for photosensitive layer are shown below.



(A-1)





(A-2)




(A-3)

Mixture of




(A-4)

Mixture of




(50wt%)




(50wt%)

(B-1)




$\bar{M}_w 50000$

(B-2)




$\bar{M}_w 150000$


(B-3)




(C-1)




(C-2)




(C-3)




(C-4)




(D-1)




(D-2)




(D-3)




(D-4)



(S-1)



(S-2)



(S-3)




TABLE 1 (Photosensitive Material)

No. of Material	A. (a weight parts)	B (b weight parts)	C	D	S	Support	Photosensitive Layer Acid Value (meq/g)
1 (Invention)	A-1 (1.7)	B-1 (1.9)	C-1	D-1	S-1	1	0.45
2 (Invention)	A-1 (1.7)	B-2 (1.9)	C-1	D-1	S-1	2	0.42
3 (Invention)	A-1 (1.5)	B-1 (2.0)	C-1	D-1	S-1	3	0.71
4 (Invention)	A-2 (2.3)	B-3 (2.0)	C-1	D-1	S-1	3	0.48
5 (Invention)	A-1 (1.7)	B-2 (1.9)	C-1	D-2	S-1	2	0.43
6 (Invention)	A-2 (1.7)	B-2 (1.9)	C-2	D-3	S-3	1	0.43
7 (Invention)	A-1 (1.7)	B-2 (1.9)	C-3	D-4	S-1	2	0.46
8 (Invention)	A-3 (1.7)	B-2 (1.9)	C-4	D-4	S-2	2	0.45
9 (Invention)	A-4 (1.7)	B-2 (1.9)	C-1	D-1	S-2	2	0.46

\* The photosensitive layer acid value was a measured value obtained by calculation from sodium hydroxide titration of the acid amount contained per g of the photosensitive layers.

#### Developing solution

[0211] The developing solution having the following composition was prepared.

#### Developing solutions 1 to 20 (Invention)

[0212] (details are shown in Table 2 below).

Alkali (X)	x g
Compound represented by formula (I) (Y)	5.0 g
Chelating agent (Z)	0.1 g
Additive 1 (P)	1.0 g
Additive 2 (Q)	1.0 g
Water	(92.9-x) g

#### Developing solutions 21 to 40 (Invention)

(details are shown in Table 2-2 below).

[0213]

Alkali (X)	x g
Compound represented by formula (I) (Y)	5.0 g
Chelating agent (Z)	0.15 g
Water	(94.85-x) g

[0214] Chelating agent (Z), additive 1 (P) and additive 2 (Q) for use in the developing solution are shown below.


(Z-1) Ethylenediaminetetraacetic acid-4Na salt

(Z-2) Citric acid

(Z-3) Hydroxyethyl ethylenediaminetriacetic acid-3K salt


[0215]

(P-1)




(P-2)  $(n)C_{15}H_{31}CO_2H$


(P-3)




(P-4)



(Q-1)




(Q-2)



```
(weight average molecular
weight: 20,000)
```

(Q-3)



(weight average molecular  
weight: 30,000)

TABLE 2

No. of Developing Solution	X (x g)	Y	Z	P	Q
1 (Invention)	NaOH (0.15)	Y-1	Z-1	None	None
2 (Invention)	KOH (0.15)	Y-1	Z-1	None	None
3 (Invention)	KOH (0.20)	Y-1	Z-1	P-1	Q-1
4 (Invention)	KOH (0.15), Monoethanolamine (1.35)	Y-1	Z-1	None	None
5 (Invention)	KOH (0.15), Triethanolamine (1.35)	Y-1	Z-1	None	None
6 (Invention)	KOH (0.15)	Y-1	None	None	None
7 (Invention)	KOH (0.15)	Y-4	Z-1	None	None
8 (Invention)	KOH (0.15)	Y-6	Z-1	None	None
9 (Invention)	KOH (0.15)	Y-7	Z-1	None	None
10 (Invention)	KOH (0.15)	Y-10	Z-1	None	None

TABLE 2 (continued)

No. of Developing Solution	X (x g)	Y	Z	P	Q
11 (Invention)	KOH (0.15)	Y-13	Z-1	None	None
12 (Invention)	KOH (0.15)	Y-17	Z-1	None	None
13 (Invention)	KOH (0.15)	Y-21	Z-1	None	None
14 (Invention)	KOH (0.15)	Y-1	Z-2	None	None
15 (Invention)	KOH (0.15)	Y-1	Z-3	None	None
16 (Invention)	KOH (0.15)	Y-1	Z-1	P-2	None
17 (Invention)	KOH (0.15)	Y-1	Z-1	P-3	None
18 (Invention)	KOH (0.15)	Y-1	Z-1	P-4	None
15 (Invention)	KOH (0.15)	Y-1	Z-1	P-2	Q-2
20 (Invention)	KOH (0.15)	Y-1	Z-1	P-2	Q-3
1 (Comp.)	KOH (0.15)	None	None	None	None
2 (Comp.)	KOH (0.15)	None	Z-1	None	None
3 (Comp.)	KOH (2.0)	Y-1	Z-1	None	None
4	Silicate-based LP-D developing solution (manufactured by Fuji Photo Film Co., Ltd.) was diluted with water 10 times				
5	Alkali-based DN-3C developing solution (manufactured by Fuji Photo Film Co., Ltd.) was diluted with water 5 times				

TABLE 2-2

No. of Developing Solution	X (x g)	Y	Z
21 (Invention)	NaOH (0.15), Na <sub>2</sub> CO <sub>3</sub> (0.16)	Y-1	Z-1
22 (Invention)	NaOH (0.06), Na <sub>2</sub> CO <sub>3</sub> (0.16)	Y-1	Z-1
23 (Invention)	KOH (0.15), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-1	Z-1
24 (Invention)	KOH (0.06), KHCO <sub>3</sub> (0.16)	Y-1	Z-1
25 (Invention)	KOH (0.06), Dry ice (0.2)	Y-1	Z-1
26 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-1	Z-1
24 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-3	Z-1
28 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-4	Z-1
29 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-5	Z-1
30 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-3	Z-2
31 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-4	Z-2
32 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-6	Z-2
33 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-7	Z-1
34 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-9	Z-2
35 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-10	Z-3
36 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-13	Z-1
37 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-15	Z-1
38 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-17	Z-1



TABLE 2-2 (continued)

No. of Developing Solution	X (x g)	Y	Z
39 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-19	Z-2
40 (Invention)	KOH (0.06), K <sub>2</sub> CO <sub>3</sub> (0.16)	Y-21	Z-3

Test of properties of developing solution

[0216] Physical properties of each developing solution shown in Table 2 was examined according to the method described in the present specification and the results obtained are shown in Table 3 below.

TABLE 3

No. of Developing Solution	pH	Electrical Conductance (mS/cm)
2 (Invention)	11.5	5
3 (Invention)	12.3	8
5 (Invention)	11.9	6
6 (Invention)	11.8	4
7 (Invention)	11.5	5
16 (Invention)	11.8	6
1 (Comparison)	11.6	5
2 (Comparison)	11.5	5
3 (Comparison)	12.8	25
4	12.8	32
5	10.0	7

Evaluation of printing

[0217] The results obtained by combining the photosensitive materials shown in Table 1 and the developing solutions shown in Tables 2 and 2-2 are shown in Tables 4 and 4-2 below.

[0218] The exposure, printing and conditions of development are shown below.

Evaluation of developing properties

[0219] The above coated photosensitive material was subjected to development without exposure, and the color of the plate was visually evaluated. If there is a residual film, the color of the photosensitive layer remains.

Evaluation of press life and resistance to printing staining

[0220] Each of the above coated photosensitive material was subjected to exposure of 100  $\mu\text{J}/\text{cm}^2$  (standard exposure condition) using FD-YAG lasers (manufactured by CSI Co., plate jet 4) of 532 nm, 100 mW, or Violet LD (internal drum type tester) of 405 nm, 30 mW on condition of 175 line/inch by 4,000 dip, and after scanning exposure of solid image and 1 to 99% dot image (every 1%), standard development was performed using an automatic processor (LP-850P2, manufactured by Fuji Photo Film Co., Ltd.) charged with various kinds of developing solutions and finishing gum solution FP-2W (manufactured by Fuji Photo Film Co., Ltd.), thus a lithographic printing plate was obtained. (Reached plate surface temperature by pre-heat after exposure was 100°C and immersion time was 15 seconds.)

[0221] Printing was performed with the obtained printing plate by printing machine R201 (manufactured by Man Roland Co., Ltd.) using GEOS-G Japanese ink (N) (manufactured by Dai-Nippon Ink & Chemicals, Inc.) and press life was evaluated by the number of the sheets which caused dot-vanishing of 3% half dot. Printing was performed by Dia IF2 printing machine (manufactured by Mitsubishi Heavy Industry Co., Ltd.) using GEOS-G scarlet (S) (manufactured by Dai-Nippon Ink & Chemicals, Inc.). The non-image domain of the printed matter was visually observed and ink-staining was evaluated.

## EP 1 172 699 A1

### Evaluation of development scum

[0222] The above coated photosensitive material (20 m<sup>2</sup>) was developed in the above developing solution (1 liter) and allowed to stand as it was for one month, and the presence of the precipitated development scum was examined. The results obtained are shown in Tables 4 and 4-2.

10

15

20

25

30

35

40

45

50

55

TABLE 4 (Results of Evaluation)

Example No.	Photosensitive Material No.	Developing Solution	Developing Properties (residual film)	Press Life	Printing Staining	Generation of Development Scum
1 (Invention)	1	1	Absent	200,000	None	None
2 (Invention)	2	2	Absent	200,000	None	None
3 (Invention)	3	2	Absent	120,000	None	None
4 (Invention)	4	2	Absent	250,000	None	None
5 (Invention)	5	2	Absent	200,000	None	None
6 (Invention)	6	2	Absent	200,000	None	None
7 (Invention)	7	2	Absent	200,000	None	None
8 (Invention)	8	2	Absent	150,000	None	None
9 (Invention)	9	2	Absent	150,000	None	None
10 (Invention)	2	1	Absent	200,000	None	None
11 (Invention)	2	3	Absent	200,000	None	None
12 (Invention)	2	4	Absent	200,000	None	None
13 (Invention)	2	5	Absent	150,000	None	None
14 (Invention)	2	6	Absent	200,000	None	None
15 (Invention)	2	7	Absent	200,000	None	None
16 (Invention)	2	8	Absent	200,000	None	None
17 (Invention)	2	9	Absent	150,000	None	None
18 (Invention)	2	10	Absent	150,000	None	None
19 (Invention)	2	11	Absent	200,000	None	None
20 (Invention)	2	12	Absent	150,000	None	None
21 (Invention)	2	13	Absent	150,000	None	None
22 (Invention)	2	14	Absent	150,000	None	None
23 (Invention)	2	15	Absent	200,000	None	None
24 (Invention)	2	16	Absent	150,000	None	None
25 (Invention)	2	17	Absent	150,000	None	None
26 (Invention)	2	18	Absent	150,000	None	None
27 (Invention)	2	19	Absent	150,000	None	None
28 (Invention)	2	20	Absent	150,000	None	None
1 (Comparison)	2	Comp. 1	Present	150,000	Stained	Precipitated
2 (Comparison)	2	Comp. 2	Present	150,000	Stained	Precipitated
3 (Comparison)	2	Comp. 3	Absent	10,000	Stained	Precipitated

Example No.	Photosensitive Material No.	Developing Solution	Developing Properties (residual film)	Press Life	Printing Staining	Generation of Development Scum
4 (Comparison)	2	Comp. 4	Absent	100,000	None	Precipitated
5 (Comparison)	2	Comp. 5	Absent	50,000	Stained	Precipitated

TABLE 4-2 (Results of Evaluation)

Example No.	Photosensi- tive Mater- ial No.	Developing Solution	Developing Properties (residual film)	Press Life	Printing Staining	Generation of Develop- ment Scum
29 (Invention)	1	26	Absent	200,000	None	None
30 (Invention)	2	26	Absent	200,000	None	None
31 (Invention)	3	26	Absent	150,000	None	None
32 (Invention)	4	26	Absent	250,000	None	None
33 (Invention)	5	26	Absent	200,000	None	None
34 (Invention)	6	26	Absent	200,000	None	None
35 (Invention)	7	26	Absent	200,000	None	None
36 (Invention)	8	26	Absent	150,000	None	None
37 (Invention)	9	26	Absent	150,000	None	None
38 (Invention)	2	21	Absent	200,000	None	None
39 (Invention)	2	22	Absent	200,000	None	None
40 (Invention)	2	23	Absent	200,000	None	None
41 (Invention)	2	24	Absent	200,000	None	None
42 (Invention)	2	25	Absent	200,000	None	None
43 (Invention)	2	27	Absent	200,000	None	None
44 (Invention)	2	28	Absent	200,000	None	None
45 (Invention)	2	29	Absent	200,000	None	None
46 (Invention)	2	30	Absent	200,000	None	None
47 (Invention)	2	31	Absent	150,000	None	None
48 (Invention)	2	32	Absent	200,000	None	None
49 (Invention)	2	33	Absent	150,000	None	None
50 (Invention)	2	34	Absent	150,000	None	None
51 (Invention)	2	35	Absent	200,000	None	None
52 (Invention)	2	36	Absent	200,000	None	None
53 (Invention)	2	37	Absent	150,000	None	None
54 (Invention)	2	38	Absent	200,000	None	None
55 (Invention)	2	39	Absent	200,000	None	None
56 (Invention)	2	40	Absent	150,000	None	None

## EP 1 172 699 A1

\* Photosensitive Materials 5 to 8 were exposed with 405 nm, Materials 1 to 4 and 9 were exposed with 532 nm.

[0223] As is apparent from the results in Tables 4 and 4-2, the developing solutions according to the present invention show good developing properties, i.e., press life and resistance to printing staining can be compatible, do not generate development scum and are excellent in processing stability.

### Examination of development behavior

[0224] Development behavior of the photosensitive material shown in Table 4 was examined according to the method described in the present specification and the results obtained are shown in Table 5 below.

TABLE 5

Example No.	Photosensitive Material	Developing Solution	Developing Speed in Unexposed Domain ( $\mu\text{m/s}$ )	Osmotic Speed of Developing Solution in Exposed Domain ( $\mu\text{m/s}$ )	Dissolution Behavior (Presence or Absence of coherent wave)
Example 2	2	2	0.2	0.005	Present
Comparative Example 1	2	Comparison 1	0.005	0.005	Absent
Comparative Example 2	2	Comparison 2	0.005	0.005	Absent
Comparative Example 3	2	Comparison 3	0.01	0.15	Absent
Comparative Example 4	2	Comparison 4	0.01	0.15	Absent
Comparative Example 5	2	Comparison 5	0.05	0.2	Absent

**EFFECT OF THE INVENTION**

[0225] According to the developing solution for a photosensitive lithographic printing plate, plate-making method and a photosensitive lithographic printing plate of the present invention, printing staining resistance and press life can be compatible without impairing image-forming properties, the compound insolubly in a developing solution can be dissolved or dispersed stable for a long period of time, and further, processing stability can be improved.


**EXAMPLE (1)**

[0226] A 1S aluminum plate having a thickness of 0.30 mm was subjected to brush-graining treatment using a No. 8 nylon brush and a suspension of 800 mesh pumice stone and water, and the surface of the plate was thoroughly washed with water. The etching was effected by immersing the plate in a 10% sodium hydroxide aqueous solution at 70°C for 60 seconds, the plate was further washed with flowing water, then washed with a 20% HNO<sub>3</sub> aqueous solution for neutralization followed by washing with water. Under the condition of V<sub>A</sub> of 12.7 V using alternating waveform electric current of sine wave, the plate was subjected to electrolytic surface roughening treatment in a 1% nitric acid aqueous solution by the quantity of electricity of 300 C/dm<sup>2</sup> at anode. The surface roughness determined was 0.45 μm (Ra). Subsequently, the plate was immersed in a 30% H<sub>2</sub>SO<sub>4</sub> aqueous solution and desmutting treatment was performed at 55°C for 2 minutes. Then, the cathode was arranged on the surface having been subjected to graining treatment in a 20% H<sub>2</sub>SO<sub>4</sub> aqueous solution at 33°C, and the plate was anodized at electric current density of 5A/dm<sup>2</sup> for 50 seconds. The anodic oxidation layer obtained had a thickness of 2.7 g/m<sup>2</sup>.

[0227] Photopolymerizable composition shown below was coated on the thus-processed aluminum plate in a dry coating weight of 1.5 g/m<sup>2</sup>, and the coated layer was dried at 100°C for 1 minute, thereby a photosensitive layer was obtained.



**Coating solution for photosensitive layer****[0228]**

Compound (A1) having ethylenically unsaturated bond	1.5 weight parts
Linear organic high polymer (B1)	2.0 weight parts
Sensitizer (C1)	0.15 weight part
Photopolymerization initiator (D1)	0.2 weight part
ε-Phthalocyanine dispersion (F1)	0.02 weight part
Fluorine-containing surfactant (Megafac F-177; manufactured by Dai-Nippon Ink & Chemicals, Inc.)	0.03 weight part
Methyl ethyl ketone	9.0 weight parts
Propylene glycol monomethyl ether acetate	7.5 weight parts
Toluene	11.0 weight parts

**A1**




B1




Mw: 150,000


C1



D1



E1



[0229] A 3 wt% aqueous solution of polyvinyl alcohol (saponification degree: 98 mol%, polymerization degree: 500) was coated on the photosensitive layer in a dry coating weight of 2.5 g/m<sup>2</sup>, and dried at 100°C for 3 minutes. Thus, a photosensitive lithographic printing plate was obtained.

[0230] The above coated photosensitive material was subjected to exposure of 100 μJ/cm<sup>2</sup> using FD-YAG lasers (manufactured by CSI Co., plate jet 4) on condition of 175 line/inch by 4,000 dip, and after scanning exposure of solid image and 1 to 99% dot image (every 1%), standard development was performed using an automatic processor (LP-850P2, manufactured by Fuji Photo Film Co., Ltd.) charged with developing solution 1 and finishing gum solution FP-2W (manufactured by Fuji Photo Film Co., Ltd.). The conditions of pre-heat were such that the plate surface temperature reached by pre-heat was 100°C, the temperature of the developing solution was 30°C and immersion time was about 15 seconds.

[0231] Developing solution 1 had the following composition, pH at 25°C was 11.5, and electrical conductance was 5 mS/cm.

Composition of developing solution 1

[0232]

Potassium hydroxide	0.15 g
Polyoxyethylene phenyl ether (n=3)	5.0 g
Chilest 400 (a chelating agent)	0.1 g
Water	94.75 g

EXAMPLES (2) TO (5)

[0233] Each lithographic printing plate was prepared in the same manner as in Example (1) except that the developing solution in Example (1) was changed to the developing solution shown in Table (1).

TABLE (1)

Example (2)	Example (3)	Example (4)	Example (5)
Potassium hydroxide: 0.15 g Polyoxyethylene methylphenyl ether (n=10): 5.0 g Chilest 400: 0.1 g Water: 94.75 g	Potassium hydroxide: 0.15 g Polyoxyethylene naphthyl ether (n=10): 5.0 g Chilest 400: 0.1 g Water: 94.75 g	Potassium hydroxide: 0.15 g Triethanolamine: 1.35 g Polyoxyethylene phenyl ether (n=12): 5.0 g Chilest 400: 0.1 g Water: 93.4 g	Potassium hydroxide: 0.2 g Polyoxyethylene naphthyl ether (n=10): 5.0 g Anon LG: 1.0 g Chilest 400: 0.1 g p-t-Butylbenzoic acid: 1 g Water: 92.3 g
pH 11.8	pH 11.7	pH 11.9	pH 12.3
electrical conductance: 5 mS/cm	electrical conductance: 5 mS/cm	electrical conductance: 5 mS/cm	electrical conductance: 5 mS/cm

[0234] A lithographic printing plate was in the same manner as in Example (1) except that linear organic high polymer B1 in photopolymerizable composition 1 in Example (1) was changed to the following B2 (Example (6)), and from polymer B1 to the following B3 (Example (7)).

B2 (Example (6)):


[0235] Allyl methacrylate/methacrylic acid (70/30 mol%) copolymer, molecular weight: 50,000

B3 (Example (7)):

[0236] Methyl methacrylate/isobutanol methacrylate/methacrylic acid (60/20/20 mol%) copolymer, molecular weight: 100,000

# EXAMPLE (8)

[0237] A lithographic printing plate was in the same manner as in Example (1) except that ethylenically unsaturated compound A1 in photopolymerizable composition 1 in Example (1) was changed to the following A2.



# EXAMPLE (9)

[0238] The following composition was mixed and stirred, heat generation was observed after about 5 minutes. After the reaction was continued for 60 minutes, the content was poured into different vessel, 30,000 weight parts of methanol was further added thereto, thus a coating solution was obtained.

## Liquid composition for undercoating

[0239]

Phosmer PE (manufactured by Uni Chemical Co. Ltd.)	20 weight parts
Methanol	130 weight parts
Water	20 weight parts
Paratoluenesulfonic acid	5 weight parts
Tetraethoxysilane	50 weight parts
3-Methacryloxypropyl triethoxysilane	50 weight parts

[0240] The coating solution was coated on the anodized aluminum support in Example (1) so that the coating amount of Si became about 0.001 g/m<sup>2</sup> and the support was dried at 100°C for 1 minute. A photosensitive layer and a water-soluble resin layer were provided on the same manner as in Example (1) and the prepared photosensitive material was subjected to exposure and development, thus a lithographic printing plate was prepared.

**COMPARATIVE EXAMPLE (1)**

[0241] A lithographic printing plate was prepared in the same manner as in Example (1) except that the composition obtained by removing polyoxyethylene phenyl ether from the developing solution 1 in Example (1) was used as the developing solution (pH 11.5, electrical conductance 5 mS/cm).

**COMPARATIVE EXAMPLE (2)**

[0242] A lithographic printing plate was prepared in the same manner as in Example (1) except that the addition amount of potassium hydroxide in developing solution 1 was changed to 2 g (pH 12.8, electrical conductance 25 mS/cm).

**COMPARATIVE EXAMPLE (3)**

[0243] A lithographic printing plate was prepared in the same manner as in Example (1) except that LP-D (manufactured by Fuji Photo Film Co., Ltd.) diluted 10 times was used as a developing solution containing alkali metal silicate in place of developing solution 1 (pH 12.8, electrical conductance 32 mS/cm).

[0244] Developing properties, press life and printing staining of the lithographic printing plates obtained in Examples (1) to (9) and Comparative Examples (1) to (3) were evaluated. The plate surface of the printing plate after development process was visually observed and the developing properties was evaluated from the presence or absence of residual film and the degree of residual film. Printing was performed with the obtained printing plate by printing machine R201 (manufactured by Man Roland Co., Ltd.) using GEOS-G Japanese ink (N) (manufactured by Dai-Nippon Ink & Chemicals, Inc.) and press life was evaluated by the number of the sheets which caused dot-vanishing of 3% half dot. Printing was performed by Dia IF2 printing machine (manufactured by Mitsubishi Heavy Industry Co., Ltd.) using GEOS-G scarlet (S) (manufactured by Dai-Nippon Ink & Chemicals, Inc.). The non-image domain of the printed matter was visually observed and staining was evaluated. The results obtained are shown in Table (2).

TABLE (2)

(Results of Evaluation of Printing Plate)			
Example No.	Developing Properties (residual film)	Press Life	Printing Staining
Example (1)	None	150,000	None
Example (2)	None	150,000	None
Example (3)	None	150,000	None
Example (4)	None	150,000	None
Example (5)	None	120,000	None
Example (6)	None	150,000	None
Example (7)	None	100,000	None
Example (8)	None	150,000	None
Example (9)	None	180,000	None
Comparative Example (1)	Slightly present	150,000	Extremely stained
Comparative Example (2)	Slightly present	10,000	Slightly stained
Comparative Example (3)	None	5,000	None

[0245] As is apparent from the results in Table (2), the lithographic printing plates according to the present invention showed satisfactory results but comparative samples were unsatisfactory at least in any item.

**EFFECT OF THE INVENTION**

[0246] As has been described, a lithographic printing plate excellent in developing properties, causing no printing staining and excellent in press life can be obtained according to the plate-making method of the present invention using a photosensitive lithographic printing plate having a photosensitive layer comprising photopolymerizable composition

and a developing solution having relatively low pH and containing a nonionic surfactant having special structure. Further, since the developing solution according to the present invention is low in pH, the influence of waste solution on environment can also be improved.

[0247] While the invention has been described in detail and with reference to specific examples thereof, it will be apparent to one skilled in the art that various changes and modifications can be made therein without departing from the spirit and scope thereof.

## Claims

1. A plate-making method of a lithographic printing plate which comprises the steps of exposure of a photosensitive lithographic printing plate having the acid value of a photosensitive layer of 1.0 meq/g or less with a laser beam, and then development with a developing solution having a pH value of 13.0 or less at a developing speed in an unexposed domain of 0.05  $\mu\text{m/s}$  or more and at an osmotic speed of a developing solution in an exposed domain of 0.1  $\mu\text{m/s}$  or less.
2. A plate-making method of a lithographic printing plate which comprises the steps of exposure of a photosensitive lithographic printing plate having the acid value of a photosensitive layer of 1.0 meq/g or less with a laser beam, and then development with a developing solution having a pH value of 13.0 or less so as to dissolve the photosensitive layer in order from the surface without swelling and peeling of the photosensitive layer.
3. A developing solution for a photosensitive lithographic printing plate which is a non-silicate-based developing solution and contains an inorganic alkali agent and a nonionic compound represented by the following formula (I):



wherein A represents a hydrophobic organic group having 1.5 or more of logP of A-H, and W represents a hydrophilic organic group having less than 1.0 of logP of W-H.



4. The developing solution for a photosensitive lithographic printing plate as claimed in claim 3, which contains a chelating agent to a divalent metal.
5. The developing solution for a photosensitive lithographic printing plate as claimed in claim 3, which has a pH of from 10.0 to 12.5 and electrical conductance of from 3 to 30 mS/cm.
6. The developing solution for a photosensitive lithographic printing plate as claimed in claim 3, which contains a carbonic acid or a carbonate.
7. The plate-making method of a lithographic printing plate as claimed in claim 1, wherein the photosensitive lithographic printing plate is a photopolymerizable lithographic printing plate having on a support a photopolymerizable photosensitive layer containing the following i) and ii) as essential components:
  - i) a compound having an addition polymerizable ethylenically unsaturated bond,
  - ii) a photopolymerization initiator.
8. The plate-making method of a lithographic printing plate as claimed in claim 2, wherein the photosensitive lithographic printing plate is a photopolymerizable lithographic printing plate having on a support a photopolymerizable photosensitive layer containing the following i) and ii) as essential components:
  - i) a compound having an addition polymerizable ethylenically unsaturated bond,
  - ii) a photopolymerization initiator.
9. The plate-making method of a lithographic printing plate as claimed in claim 7, wherein the photopolymerizable photosensitive layer contains a titanocene-based initiator or a colorant such as a pigment.
10. The plate-making method of a lithographic printing plate as claimed in claim 8, wherein the photopolymerizable photosensitive layer contains a titanocene-based initiator or a colorant such as a pigment.

11. The plate-making method of a lithographic printing plate as claimed in claim 7, wherein the support is an anodized aluminum support containing an organic compound having a phosphorus-containing atomic group on the surface of the support.

12. The plate-making method of a lithographic printing plate as claimed in claim 8, wherein the support is an anodized aluminum support containing an organic compound having a phosphorus-containing atomic group on the surface of the support.

13. A photosensitive lithographic printing plate comprising a photopolymerizable photosensitive layer, wherein the photosensitive layer contains a compound having an acid radical having a pKa of 9 or less and the acid value of the photosensitive layer is from 0.20 to 0.60 meq/g.

14. A plate-making method of a lithographic printing plate which comprises the steps of exposure of a photosensitive lithographic printing plate comprising a support having an anodized film on the surface having provided thereon a photopolymerizable photosensitive layer containing a compound having an addition polymerizable ethylenically unsaturated double bond, a high polymer soluble or swelling in an alkali aqueous solution, and a photopolymerization initiator with a laser beam, and then development with a developing solution comprising an alkali aqueous solution containing at least one of a nonionic aromatic ether-based activator represented by the following formula (I-A) and a nonionic aromatic ether-based activator represented by the following formula (I-B):



wherein  $R_1$  and  $R_2$  each represents H or an alkyl group having from 1 to 100 carbon atoms, and  $n$  and  $m$  each represents an integer of from 0 to 100.

15. A plate-making method of a lithographic printing plate which comprises the steps of image exposure of a photosensitive lithographic printing plate comprising an aluminum support having provided thereon a photopolymerizable photosensitive layer containing a compound having an ethylenically unsaturated double bond, a photopolymerization initiator and a high polymer binder, and then development with a developing solution containing an inorganic alkali agent and a nonionic surfactant having a polyoxyalkylene ether group, having a pH of from 10.0 to 12.5, and an electrical conductance of from 3 to 30 mS/cm.

Fig. 1





Fig. 2



B: Photosensitive material in which the developing solution is easily immersed.

$t_B$ : Time in which electrostatic capacity is changed.

A: Photosensitive material in which the developing solution is immersed with difficulty.

$T_a$ : Time in which electrostatic capacity is changed.



Fig. 3

The change of the film thickness is detected by the coherent






Fig. 4



(Coherent Wave o): Invention



(Coherent Wave x): Conventional



European Patent  
Office

# PARTIAL EUROPEAN SEARCH REPORT

Application Number

which under Rule 45 of the European Patent Convention shall be considered, for the purposes of subsequent proceedings, as the European search report

EP 01 11 5798

DOCUMENTS CONSIDERED TO BE RELEVANT			
Category	Citation of document with indication, where appropriate, of relevant passages	Relevant to claim	CLASSIFICATION OF THE APPLICATION (Int.Cl.7)
X	EP 0 949 540 A (FUJI PHOTO FILM CO LTD) 13 October 1999 (1999-10-13) * page 166, paragraphs 19,180,239-246; claims *	2,8,10, 12,13	G03F7/32 G03F7/032 G03F7/033 G03F7/035
X	* paragraphs '0190!', '0191!' *	3,14	
X	US 5 834 156 A (KANADA EIJI ET AL) 10 November 1998 (1998-11-10) * column 25, line 53 - line 55; example 8 *	3	
P,X	EP 1 091 251 A (FUJI PHOTO FILM CO LTD) 11 April 2001 (2001-04-11) * paragraphs '0171!', '0142!', '0140!', '0144!'; examples *	2,8,10, 13	
P,X	* paragraphs '0101!'-'0106!' *	3,4,14	
P,X	EP 1 070 990 A (FUJI PHOTO FILM CO LTD) 24 January 2001 (2001-01-24) * paragraph '0141!'; examples *	2	
P,X	* page 33, paragraph 65 *	13	
	-/--		
			TECHNICAL FIELDS SEARCHED (Int.Cl.7)
			G03F
INCOMPLETE SEARCH			
<p>The Search Division considers that the present application, or one or more of its claims, does/do not comply with the EPC to such an extent that a meaningful search into the state of the art cannot be carried out, or can only be carried out partially, for these claims.</p> <p>Claims searched completely :</p> <p>Claims searched incompletely :</p> <p>Claims not searched :</p> <p>Reason for the limitation of the search:</p> <p style="text-align: center;">see sheet C</p>			
Place of search		Date of completion of the search	Examiner
THE HAGUE		30 October 2001	Heywood, C
CATEGORY OF CITED DOCUMENTS			
<p>X : particularly relevant if taken alone  Y : particularly relevant if combined with another document of the same category  A : technological background  O : non-written disclosure  P : intermediate document</p>			
<p>T : theory or principle underlying the invention  E : earlier patent document, but published on, or after the filing date  D : document cited in the application  L : document cited for other reasons</p>			
<p>&amp; : member of the same patent family, corresponding document</p>			

EPO FORM 1503 03/92 (P/C01)



European Patent  
Office

INCOMPLETE SEARCH  
SHEET C

Application Number  
EP 01 11 5798

Claim(s) searched completely:  
2,3,4,5,6,8,10,12,13,14,15

Claim(s) searched incompletely:  
1,7,9,11

Reason for the limitation of the search:

Present claims 1,7,9,11 relate to a method defined by reference to desirable characteristics or properties of a developing solution. Namely developing speed in an unexposed region and osmotic speed of a developing solution in an exposed region.

The claims cover all methods having developers with these characteristics or properties, whereas the application provides support within the meaning of Article 84 EPC and/or disclosure within the meaning of Article 83 EPC for only a very limited number of such methods. In the present case, the claims so lack support, and the application so lacks disclosure, that a meaningful search over the whole of the claimed scope is impossible. Independent of the above reasoning, the claims also lack clarity (Article 84 EPC). An attempt is made to define the method by reference to a result to be achieved. Again, this lack of clarity in the present case is such as to render a meaningful search over the whole of the claimed scope impossible. Consequently, the search has been carried out for those parts of the claims which appear to be clear, supported and disclosed, namely those parts relating to the examples.

## PARTIAL EUROPEAN SEARCH REPORT

Application Number  
EP 01 11 5798

DOCUMENTS CONSIDERED TO BE RELEVANT			CLASSIFICATION OF THE APPLICATION (Int.Cl.7)
Category	Citation of document with indication, where appropriate, of relevant passages	Relevant to claim	
X	EP 0 820 840 A (FUJI PHOTO FILM CO LTD) 28 January 1998 (1998-01-28) * page 11, line 15 *	2	
P,X	EP 1 048 982 A (FUJI PHOTO FILM CO LTD) 2 November 2000 (2000-11-02) * paragraphs '0318!', '0319!'; examples; tables III-2 *	2,8,10	
P,X	* paragraphs '0317!', '0276!'; examples *	13	
P,X	EP 1 035 435 A (FUJI PHOTO FILM CO LTD) 13 September 2000 (2000-09-13) * paragraph '0101!'; examples; table 2 *	2	
P,X	* paragraphs '0205!'- '0207!'; table 2 *	13	TECHNICAL FIELDS SEARCHED (Int.Cl.7)
P,X	US 6 180 322 B1 (IIJIMA TAKAHIRO ET AL) 30 January 2001 (2001-01-30) * column 3, line 40 - column 4, line 23; examples *	3	
X	& JP 11 249322 A (JSR CORP) 17 September 1997 (1997-09-17)	3	
P,X	US 6 100 016 A (DENZINGER STEFFEN ET AL) 8 August 2000 (2000-08-08) * column 9, line 9 - line 15; claim 1; table II *	3,4	
X	EP 0 953 880 A (NICHIGO MORTON CO LTD) 3 November 1999 (1999-11-03) * paragraphs '0008!', '0011!'; claims *	3,14	
X	US 4 098 712 A (IKEDA TOMOAKI ET AL) 4 July 1978 (1978-07-04) * claim 2; examples 1,6,7 *	3,14	
X	US 3 586 504 A (COATES ALFRED E ET AL) 22 June 1971 (1971-06-22) * claims; examples 7-10 *	3	



European Patent  
Office

## PARTIAL EUROPEAN SEARCH REPORT

Application Number  
EP 01 11 5798

DOCUMENTS CONSIDERED TO BE RELEVANT			CLASSIFICATION OF THE APPLICATION (Int.Cl.7)
Category	Citation of document with indication, where appropriate, of relevant passages	Relevant to claim	
X	GB 1 591 988 A (VICKERS LTD) 1 July 1981 (1981-07-01) * example 2 *	3	
X	WO 87 04810 A (HUGHES AIRCRAFT CO) 13 August 1987 (1987-08-13) * tables V-C, V-E *	3	
X	EP 0 602 736 A (EASTMAN KODAK CO) 22 June 1994 (1994-06-22) * page 12, line 25 - line 45 *	3	
X	EP 0 924 570 A (FUJI PHOTO FILM CO LTD) 23 June 1999 (1999-06-23) * paragraph '0123!'; examples; table 1 *	2	TECHNICAL FIELDS SEARCHED (Int.Cl.7)
X	DATABASE WPI Section Ch, Week 198607 Derwent Publications Ltd., London, GB; Class A89, AN 1986-045178 XP002180972 -& JP 60 263147 A (DAINIPPON INK & CHEM KK), 26 December 1985 (1985-12-26) * abstract *	3	

EPO FORM 1503 03.92 (P/M/C10)

**ANNEX TO THE EUROPEAN SEARCH REPORT  
ON EUROPEAN PATENT APPLICATION NO.**

EP 01 11 5798

This annex lists the patent family members relating to the patent documents cited in the above-mentioned European search report. The members are as contained in the European Patent Office EDP file on  
The European Patent Office is in no way liable for these particulars which are merely given for the purpose of information.

30-10-2001

Patent document cited in search report		Publication date		Patent family member(s)	Publication date
EP 0949540	A	13-10-1999	JP	11352691 A	24-12-1999
			EP	0949540 A1	13-10-1999
US 5834156	A	10-11-1998	DE	4480342 T0	11-01-1996
			WO	9518400 A1	06-07-1995
EP 1091251	A	11-04-2001	JP	2001175001 A	29-06-2001
			JP	2001209170 A	03-08-2001
			EP	1091251 A2	11-04-2001
EP 1070990	A	24-01-2001	JP	2001033961 A	09-02-2001
			EP	1070990 A1	24-01-2001
EP 0820840	A	28-01-1998	JP	10035130 A	10-02-1998
			JP	10100556 A	21-04-1998
			US	6258410 B1	10-07-2001
			EP	0820840 A2	28-01-1998
EP 1048982	A	02-11-2000	JP	2000309724 A	07-11-2000
			JP	2001042524 A	16-02-2001
			JP	2001100412 A	13-04-2001
			EP	1048982 A1	02-11-2000
EP 1035435	A	13-09-2000	JP	2000258910 A	22-09-2000
			EP	1035435 A2	13-09-2000
US 6180322	B1	30-01-2001	JP	11249322 A	17-09-1999
US 6100016	A	08-08-2000	EP	1085381 A1	21-03-2001
			JP	2001133991 A	18-05-2001
EP 0953880	A	03-11-1999	US	5922522 A	13-07-1999
			BR	9901322 A	14-03-2000
			CN	1233783 A	03-11-1999
			EP	0953880 A2	03-11-1999
US 4098712	A	04-07-1978	JP	52099101 A	19-08-1977
			DE	2706634 A1	18-08-1977
			GB	1574620 A	10-09-1980
US 3586504	A	22-06-1971	FR	2028658 A5	16-10-1970
GB 1591988	A	01-07-1981	NONE		
WO 8704810	A	13-08-1987	DE	3684147 D1	09-04-1992
			EP	0256031 A1	24-02-1988

EPO FORM P0459

For more details about this annex : see Official Journal of the European Patent Office, No. 12/82

**ANNEX TO THE EUROPEAN SEARCH REPORT  
ON EUROPEAN PATENT APPLICATION NO.**

EP 01 11 5798

This annex lists the patent family members relating to the patent documents cited in the above-mentioned European search report. The members are as contained in the European Patent Office EDP file on  
The European Patent Office is in no way liable for these particulars which are merely given for the purpose of information.

30-10-2001

Patent document cited in search report		Publication date	Patent family member(s)	Publication date
WO 8704810	A		JP 1050896 B	01-11-1989
			JP 63502780 T	13-10-1988
			US 4777119 A	11-10-1988
			WO 8704810 A1	13-08-1987
EP 0602736	A	22-06-1994	DE 69315046 D1	11-12-1997
			DE 69315046 T2	04-06-1998
			EP 0602736 A2	22-06-1994
			JP 6222568 A	12-08-1994
			US 5466559 A	14-11-1995
EP 0924570	A	23-06-1999	JP 11171907 A	29-06-1999
			EP 0924570 A1	23-06-1999
			US 6153660 A	28-11-2000
JP 60263147	A	26-12-1985	NONE	

EPO FORM P0459

For more details about this annex : see Official Journal of the European Patent Office, No. 12/82